47	KSRB 7.12 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using four track window frame of size 122.2x31.75mm for bottom section 1.1mm thick, weight 1.205 kg/m, sides and top sections 1.2 mm thick weight 1.093 kg/m, shutter section comprising top and bottom section of size 40mmx18mm wall thickness 1.25mm weight 0.417 kg /m, shutter side outer 40mmx18mm wall thickness 1.25mm weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm weight 0.469 kg/m, shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles, tower bolts etc., providing and fixing 5.5mm thick plain glass for shutters fitted with rubber beading including cutting to required length, joints mitred subdividing the frame, tenoned and riveted in the assembled frame to be stiffened with end clips at corners, angles etc., fixed to the walls, lintels, floor beams,cills, as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any rust and coated with greasy materials for non adhesion of mortar and other sticky materials, (this coating should be cleaned after installation) including cost of materials, fixtures, labour and HOM complete as per									
		Sqm	1	1	45.27			45.27		
48	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on existing flooring with special adhesive for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, cost of materials, mortar, labour etc., complete as per specification.									
	Ground Floor									
	GentsToilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	Ladies Toilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	First Floor									
	GentsToilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	Ladies Toilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
						Total Qty Work Done		72.03	1228.00	88452.84
49	Providing and fixing Vitrified glazed tiles of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on existing flooring with special adhesive for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, cost of materials, mortar, labour etc., complete as per specification.									
	Second Floor									
	GentsToilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	Ladies Toilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	Third Floor									
	GentsToilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
	Ladies Toilet	Sqm	1	2	1.45	1.50		4.35		
		Sqm	1	3	1.45	1.20		5.22		
		Sqm	1	1	6.75	1.25		8.44		
						Total Qty Work Done		72.03		
						Upto 125%		72.03	1228.00	88452.84
50	*Providing skirting, dadoing, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Colour glazed tiles 15x15 cms 6mm thick*									
	Ground Floor									
	GentsToilet	Sqm	1	2	5.90		2.35	27.73		

Scanned with CamScanner

		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Ladies Toilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Deduct Door	Sqm	2	1	1.20		2.35	-5.64		
		Sqm	2	5	0.90		2.10	-18.9		
	First Floor									
	GentsToilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Ladies Toilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Deduct Door	Sqm	2	1	1.20		2.35	-5.64		
		Sqm	2	5	0.90		2.10	-18.9		
					Total Qty Work Done			361.70		
					Upto 125%			107.03	1534.00	164176.35
					Above 125%			254.68	1508.58	384196.42
51	Providing skirting, dadoing, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Colour glazed tiles 15x15 cms 6mm thick									
	Second Floor									
	GentsToilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Ladies Toilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Deduct Door	Sqm	2	1	1.20		2.35	-5.64		
		Sqm	2	5	0.90		2.10	-18.9		
	Third Floor									
	GentsToilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Ladies Toilet	Sqm	1	2	5.90		2.35	27.73		
		Sqm	1	3	5.30		2.35	37.365		
		Sqm	1	1	16.00		2.35	37.6		
	Deduct Door	Sqm	2	1	1.20		2.35	-5.64		
		Sqm	2	5	0.90		2.10	-18.9		
					Total Qty Work Done			361.70		
					Upto 125%			213.59	1540.00	328924.75
					Above 125%			148.11	1510.95	223790.46
52	Providing and laying flooring using prepolished, gang saw/water cut 19mm thick granite laid with a bed of 20mm thick 1:4 cm & jointed ith neat cement slurry mixed with pigment to mach shade of granite slabs including laying POP on finished surface and cleaning the surface, including the cost of all materials, mortar and labours etc., complete as per specifications.-do- using silver grey granite I Multy Red I Ruby Red I Black I Hassan Green I River Pink Granite of width not less than 1200mm									
	Ground Floor									
	Room 1,2,3,4,5,6	Sqm	6	1	5.45	6.85		224.00		
	Skirting	Sqm	6	1	24.5		0.15	22.05		
	Door piece	Sqm	6	1	1.04	0.12		0.75		
	Dudect									
	Door	Sqm	6	1	1.2		0.15	-1.08		
	Column	Sqm	6	1	0.6	0.05		-0.18		
	Store Room (Landscape)	Sqm	1	1	4.2	6.85		28.77		
	Skirting	Sqm	1	1	22.1		0.15	3.32		

Scanned with CamScanner

	Door piece	Sqm	1	1	1.04	0.12		0.12		
	Dudect									
	Door	Sqm	1	1	1.2		0.15	-0.18		
	Column	Sqm	1	2	0.6	0.05		-0.06		
	Passage			1						
		Sqm	1	2	8.6	2.15		36.98		
		Sqm	1	1	26.5	2.75		72.88		
	Skirting	Sqm	1	1	48		0.15	7.20		
	Dudect									
	Door	Sqm	1	10	1.2		0.15	-1.80		
	Lobby	Sqm	1	1	6.55		0.15	-0.98		
	Sttair Case Area	Sqm	1	2	3.4		0.15	-1.02		
	Room 6 &7									
		Sqm	2	1	8.38	7.72		129.39		
		Sqm	2	1	1.5	0.55		1.65		
		Sqm	2	1	2	0.55		2.20		
		Sqm	2	2	1.33	0.55		2.93		
	Skirting	Sqm	2	1	37.8		0.15	11.34		
	Door piece	Sqm	2	1	1.04	0.12		0.25		
	Dudect									
	Door	Sqm	2	1	1.2		0.15	-0.36		
	Column	Sqm	2	1	0.6	0.2		-0.24		
	Office 1 & 2									
		Sqm	2	1	6.27	6.4		80.26		
		Sqm	2	1	1.99	0.55		2.19		
		Sqm	2	1	1.35	0.55		1.49		
	Skirting	Sqm	2	1	29.74		0.15	8.92		
	Door piece	Sqm	2	1	1.04	0.12		0.25		
	Dudect									
	Door	Sqm	2	1	1.2		0.15	-0.36		
	Column	Sqm	2	1	0.6	0.05		-0.06		
	Enterence Lobby									
		Sqm	1	1	6.55	6.3		41.27		
	Skirting	Sqm	1	1	14.08		0.15	2.11		
	Door piece	Sqm	1	1	1.04	0.12		0.12		
	Dudect									
	Door	Sqm	1	1	1.2		0.15	-0.18		
		Sqm	1	2	1.99	0.55		-2.19		
	Enterence									
		Sqm	1	1	6.55	5.9		38.65		
	Skirting	Sqm	1	2	1.64		0.15	0.49		
	Stair Case Area	Sqm	2	1	3.4	4.61		31.35		
	Skirting	Sqm	2	1	12.62		0.15	3.79		
	StairCase Tread	Sqm	2	11	1.5	0.275		9.08		
	Raiser	Sqm	2	12	1.5		0.15	5.40		
	Landing	Sqm	2	1	3.4	1.63		11.08		
	StairCase Tread	Sqm	2	10	1.5	0.275		8.25		
	Raiser	Sqm	2	11	1.5		0.15	4.95		
	Skirting	Sqm	2	23	0.45		0.15	3.11		
		Sqm	2	1	6.66		0.15	2.00		
	StairCase Tread	Sqm	2	11	1.5	0.275		9.08		
	Raiser	Sqm	2	12	1.5		0.15	5.40		
	Landing	Sqm	2	1	3.4	1.63		11.08		
	StairCase Tread	Sqm	2	10	1.5	0.275		8.25		
	Raiser	Sqm	2	11	1.5		0.15	4.95		
	Skirting	Sqm	2	23	0.45		0.15	3.11		

Scanned with CamScanner

		Sqm	2	1	6.66		0.15	2.00		
	StairCase Tread Second Floor	Sqm	2	11	1.5	0.275		9.08		
	Raiser	Sqm	2	12	1.5		0.15	5.40		
	Landing	Sqm	2	1	3.4	1.63		11.08		
	StairCase Tread	Sqm	2	10	1.5	0.275		8.25		
	Raiser	Sqm	2	11	1.5		0.15	4.95		
	Skirting	Sqm	2	23	0.45		0.15	3.11		
		Sqm	2	1	6.66		0.15	2.00		
	StairCase Tread Third	Sqm	2	11	1.5	0.275		9.08		
	Raiser	Sqm	2	12	1.5		0.15	5.40		
	Landing	Sqm	2	1	3.4	1.63		11.08		
	StairCase Tread	Sqm	2	10	1.5	0.275		8.25		
	Raiser	Sqm	2	11	1.5		0.15	4.95		
	Skirting	Sqm	2	23	0.45		0.15	3.11		
		Sqm	2	1	6.66		0.15	2.00		
	Connection Slab Ground Flo	Sqm	1	2	2.60	4.5		23.40		
	Connection Slab First Floor	Sqm	1	2	2.50	3.5		17.50		
								962.34	3360.00	3233470.13
53	KSRB 9-27.1: Fixing Door frame in an existing opening including embedding frame in floor and walls after cutting masonry for hold fasts for embedding hold fast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coat tar to sides of frame, making good the damages to wall and floor as required and disposal of the debris with lead upto 50m. including cost of materials, labour charges, complete as per specifications. (P-61, I-9.80)									
	Second & Third Floor									
	D1 frame	Nos	1	8				8.00		
		Nos	1	8				8.00		
	Toilet Room	Nos	4	2				8.00		
	Head Room	Nos	1	1				1.00		
					Total Qty Work Done			25.00		
					Upto 125%			13.00	1621.00	21073.00
					Above125%			12.00	1630.83	19569.96
54	Providing and fixing 65mmx125mm GRP Doorframe fabricated using E-Glass Chopped Strand Mat (CSM) U.V.Stabilized Isopthalic Gel coat and Isopthalic resin. The Thickness of the GRP Skin shall not be less than 2.0mm. The Door frame consists of four segments, which are provided with plug-in-socket arrangement in situ in the mould. The segments are plugged in and are joined together by means of screws. The GRP frame shall be provided with wooden reinforcement on 6 locations for high screw holding capacity for fixing metallic hold fast and shall be consolidated by filling with medium density foam/Plaster of Paris with fibre reinforcement. Six numbers of 260x25x5mm size S Shaped M.S.Flat hold fast, Hold fast shall be provided with the frame. (PWD SR -2016-17, P-65/I-9.96)									
	Ground Floor									
	GentsToilet	Sqm	1	5	5.70			28.50		
	Ladies Toilet	Sqm	1	5	5.70			28.50		
	First Floor									
	GentsToilet	Sqm	1	5	5.70			28.50		
	Ladies Toilet	Sqm	1	5	5.70			28.50		
	Second Floor									
	GentsToilet	Sqm	1	5	5.70			28.50		
	Ladies Toilet	Sqm	1	5	5.70			28.50		
	Third Floor									
	GentsToilet	Sqm	1	5	5.70			28.50		
	Ladies Toilet	Sqm	1	5	5.70			28.50		
					Total Qty Work Done			228.00		
					Upto 125%			222.38	653.00	145210.88
					Above 125%			5.63	652.81	3672.03

Scanned with CamScanner

55	P/F Factory made single leaf rigid GRP Sandwich composite door shutter of 32mm thick, laminated with two GRP skins with wood grain finish, fabricated using U.V-stabilized isopthalic Gel coat and on layer of 45gsm E-Glass Chopped strand Mat (CSM) impregnated with orthopthalick polyster resin. The thickness of the skins shall not be less than 1 5mm. Expanded Polystyrene (EPS) structural foam panel of 29mm thickness and a density of 20 kg/m3 shall be used as core material. Wooden reinforcements made of Seasoned Sal wood block of cross section not less than 28mm x 32mm and also necessary sal wood reinforcement for fixing the metal fittings such as tower bolts, aldrops, handles, etc., shall be provided. A structural adhesive compatible with EPS foam shall be used for bonding the core material, the sal wood reinforcement and the skins. The material and process for manufacturing the door shutters shall confirm to RV/TIFAC Composites Design centre Standards and specifications and the door shutters tested in confirmation to IS 4020-1994. The finish of shutter will be plain colour										
	Ground Floor										
	GentsToilet	Sqm	1	5	0.75		2.10	7.88			
	Ladies Toilet	Sqm	1	5	0.75		2.10	7.88			
	First Floor							0.00			
	GentsToilet	Sqm	1	5	0.75		2.10	7.88			
	Ladies Toilet	Sqm	1	5	0.75		2.10	7.88			
	Second Floor							0.00			
	GentsToilet	Sqm	1	5	0.75		2.10	7.88			
	Ladies Toilet	Sqm	1	5	0.75		2.10	7.88			
	Third Floor							0.00			
	GentsToilet	Sqm	1	5	0.75		2.10	7.88			
	Ladies Toilet	Sqm	1	5	0.75		2.10	7.88			
					Total Qty Work Done			63.00			
					Upto 125%			62.60	3561.00		222918.60
					Above 125%			0.40	3560.76		1424.30
56	KSRB 15-17.4: Applying **priming coat over new wood surface** and /or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour , complete as per specifications (Page-115/I-15.58)										
		Sqm	2	11	1.05	0.4		9.24			
		Sqm	2	11	2.4	0.4		21.12			
	Door Shutters	Sqm	1	11	1.05	2.05		23.678			
					Total Qty Work Done			54.038			
					Upto 125%			54.038	59.00		3188.21
57	KSRB 15-17.6: Providing and applying **painting two coats** (excluding priming coat on new wood surface and /or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per										
	Door Frame	Sqm	2	11	1.05	0.4		9.24			
		Sqm	2	11	2.4	0.4		21.12			
	Door Shutters	Sqm	1	11	1.05	2.05		23.678			
					Total Qty Work Done			54.038			
					Upto 125%			54.038	121.00		6538.54
58	KSRB 7.9 : Providing and fixing M.S. grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 (page no. 34. Item no.7.9 PWD-S.R 2018-19)										
	Second Floor										
	Windows										
	Room 1,4										
	W3	Sqm	2	6	1.50	1.5		27.00			
	Room 2,3										
	W3	Sqm	2	3	1.50	1.5		13.50			
	Passage										
	W2	Sqm	2	1	1.50	1.5		4.50			
	Room 5,6										
		Sqm	2	3	1.20	1.5		10.80			
		Sqm	2	2	1.50	1.5		9.00			
	Room 7,8										
		Sqm	2	1	1.50	1.5		4.50			
		Sqm	2	4	1.80	1.5		21.60			
	Third Floor										
	Windows										

Scanned with CamScanner

	Room 1,4									
	W3	Sqm	2	6	1.50	1.5		27.00		
	Room 2,3									
	W3	Sqm	2	3	1.50	1.5		13.50		
	Passage									
	W2	Sqm	2	1	1.50	1.5		4.50		
	Room 5,6									
		Sqm	2	3	1.20	1.5		10.80		
		Sqm	2	2	1.50	1.5		9.00		
	Room 7,8									
		Sqm	2	1	1.50	1.5		4.50		
		Sqm	2	4	1.80	1.5		21.60		
	First Floor Toilet Romm	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	Second Floor Toilet Romm	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	Third Floor Toilet Romm	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	StairCase	Sqm	2	4	1.20		1.50	14.40		
	Head Room									
	Windows	Sqm	1	1	1.20		1.50	1.80		
	Windows	Sqm	1	1	1.20		1.50	1.80		
	Windows	Sqm	1	2	1.50		1.50	4.50		
						Sqm	Qty	236.34		
			74.76X21 kg/m			Total Qty Work Done		4963.14		
						Upto 125%		1679.74	113.00	189810.34
						Above125%		3283.40	127.00	416993.56
59	Providing and Applying enamel metal Paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter including cost of materials labour complete as per specification									
	Ground Floor Windows									
	Room 1									
	W3	Sqm	1	2	1.5	1.5		4.50		
	Ventilator	Sqm	1	1	1.2	0.3		0.36		
	Room 2,3,4,5,6									
	W3	Sqm	5	2	1.5	1.5		22.50		
	Ventilator	Sqm	5	1	1.2	0.3		1.80		
	Store Room									
		Sqm	1	2	1.2	1.5		3.60		
	Passage									
	W2	Sqm	1	2	1.5	1.5		4.50		
	Room 7,8									
		Sqm	2	2	1.2	1.5		7.20		
	Office 1&2									
		Sqm	2	4	1.8	1.5		21.60		
	First Floor Windows									
	Room 1									
	W3	Sqm	1	3	1.5	1.5		6.75		
	Ventilator	Sqm	1	1	1.2	0.3		0.36		
	Room 2,3,4							0.00		
	W3	Sqm	3	3	1.5	1.5		20.25		
	Ventilator	Sqm	3	1	1.2	0.3		1.08		
	Store Room							0.00		
		Sqm	1	1	1.2	1.5		1.80		
	Room 7,8							0.00		
		Sqm	2	3	1.2	1.5		10.80		
	Office 1&2							0.00		
		Sqm	2	4	1.8	1.5		21.60		
	Ventilator	Sqm	4	1	1.2	0.45		2.16		

Scanned with CamScanner

	Second Floor							0.00		
	Windows							0.00		
	Room 1,4							0.00		
	W3	Sqm	2	6	1.50	1.5		27.00		
	Room 2,3							0.00		
	W3	Sqm	2	3	1.50	1.5		13.50		
	Passage							0.00		
	W2	Sqm	2	1	1.50	1.5		4.50		
	Room 5,6							0.00		
		Sqm	2	3	1.20	1.5		10.80		
		Sqm	2	2	1.50	1.5		9.00		
	Room 7,8							0.00		
		Sqm	2	1	1.50	1.5		4.50		
		Sqm	2	4	1.80	1.5		21.60		
	Third Floor Windows							0.00		
	Room 1,4							0.00		
	W3	Sqm	2	6	1.50	1.5		27.00		
	Room 2,3							0.00		
	W3	Sqm	2	3	1.50	1.5		13.50		
	Passage							0.00		
	W2	Sqm	2	1	1.50	1.5		4.50		
	Room 5,6							0.00		
		Sqm	2	3	1.20	1.5		10.80		
		Sqm	2	2	1.50	1.5		9.00		
	Room 7,8							0.00		
		Sqm	2	1	1.50	1.5		4.50		
		Sqm	2	4	1.80	1.5		21.60		
	First Floor Toilet Room	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	Second Floor Toilet Room	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	Third Floor Toilet Room	Sqm	2	1	6.15		0.60	7.38		
		Sqm	2	1	2.75		0.60	3.30		
	Head Room							0.00		
	Windows	Sqm	1	1	1.50		1.50	2.25		
	Windows	Sqm	1	1	1.20		1.50	1.80		
	Windows	Sqm	1	2	1.50		1.50	4.50		
					Total Qty Work Done			353.25	113	39917.25
60	KSRB 15-7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (page no.117. item no.15.33 S.R 2018-19)									
	Wall									
	Ground Floor Toilet Room	Sqm	2	2	2.75		3.40	37.40		
		Sqm	2	2	6.75		3.40	91.80		
	Offset Column	Sqm	2	4	0.05		2.95	1.18		
	Deduct	Sqm	2	2	2.75		2.40	-26.40		
		Sqm	2	2	6.75		2.40	-64.80		
	First Floor Toilet Room	Sqm	2	2	2.75		3.40	37.40		
		Sqm	2	2	6.75		3.40	91.80		
	Offset Column	Sqm	2	4	0.05		2.95	1.18		
	Deduct	Sqm	2	2	2.75		2.40	-26.40		
		Sqm	2	2	6.75		2.40	-64.80		
	Second Floor Toilet Room	Sqm	2	2	2.75		3.40	37.40		
		Sqm	2	2	6.75		3.40	91.80		
	Offset Column	Sqm	2	4	0.05		2.95	1.18		
	Deduct	Sqm	2	2	2.75		2.40	-26.40		
		Sqm	2	2	6.75		2.40	-64.80		
	Third Floor Toilet Room	Sqm	2	2	2.75		3.40	37.40		
		Sqm	2	2	6.75		3.40	91.80		
	Offset Column	Sqm	2	4	0.05		2.95	1.18		
	Deduct	Sqm	2	2	2.75		2.40	-26.40		
		Sqm	2	2	6.75		2.40	-64.80		
	Ceiling									
	Ground Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13		

Scanned with CamScanner

	First Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13		
	Second Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13		
	Third Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13		
	Head Room 1,2	Sqm	2	1	3.40	4.96		33.73		
	Head Room 3	Sqm	1	1	6.55	8.55		56.00		
	Second Floor									
	Room 1 & 4									
		Sqm	2	2	6.75	5.4		145.80		
	Beam	Sqm	2	2	6.75	1.1		29.70		
	Room 2& 3							0.00		
		Sqm	2	2	6.75	5.4		145.80		
		Sqm	2	2	6.75	1.98		53.46		
	Beam	Sqm	2	2	6.75	1.1		29.70		
	Room 5&8							0.00		
		Sqm	2	1	7.62	6.85		104.39		
		Sqm	2	1	1.30	7.62		19.81		
		Sqm	2	1	0.55	1.5		1.65		
		Sqm	2	1	0.55	2		2.20		
	Beam	Sqm	2	2	7.62	1.1		33.53		
	Stair case Room							0.00		
	Staircase Room 5th Flight	Sqm	1	1	1.50	3.25		4.88		
	6th Flight	Sqm	1	1	1.50	3.75		5.63		
	Landing	Sqm	1	1	1.35	3.4		4.59		
	Passage							0.00		
		Sqm	1	2	8.55	2.15		36.77		
		Sqm	1	1	26.50	2.75		72.88		
	Room 6&7									
	Long Wall	Sqm	2	1	6.17	6.3		77.74		
		Sqm	2	1	3.20	6.3		40.32		
		Sqm	2	1	0.55	1.3		1.43		
	Beam	Sqm	2	1	1.40	6.3		17.64		
	Third Floor									
	Room 1 & 4									
		Sqm	2	2	6.75	5.4		145.80		
	Beam	Sqm	2	2	6.75	1.1		29.70		
	Room 2& 3							0.00		
		Sqm	2	2	6.75	5.4		145.80		
		Sqm	2	2	6.75	1.98		53.46		
	Beam	Sqm	2	2	6.75	1.1		29.70		
	Room 5&8							0.00		
		Sqm	2	1	7.62	6.85		104.39		
		Sqm	2	1	1.30	7.62		19.81		
		Sqm	2	1	0.55	1.5		1.65		
		Sqm	2	1	0.55	2		2.20		
	Beam	Sqm	2	2	7.62	1.1		33.53		
	Stair case Room							0.00		
	Staircase Room 5th Flight	Sqm	1	1	1.50	3.25		4.88		
	6th Flight	Sqm	1	1	1.50	3.75		5.63		
	Landing	Sqm	1	1	1.35	3.4		4.59		
	Passage							0.00		
		Sqm	1	2	8.55	2.15		36.77		
		Sqm	1	1	26.50	2.75		72.88		
	Room 6&7									

Scanned with CamScanner

	Long Wall	Sqm	2	1	6.17	6.3		77.74		
		Sqm	2	1	3.20	6.3		40.32		
		Sqm	2	1	0.55	1.3		1.43		
	Beam	Sqm	2	1	1.40	6.3		17.64		
					Total Qty Work Done			2050.76		
					Upto 125%			2050.76	38.00	77928.98
61	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.									
	Ground Floor									
	Room 1,2,3,4,5, Gents Toilet									
	Short Wall	Sqm	6	2	5.4		3.3	213.84		
	Long Wall	Sqm	6	2	6.8		3.3	269.28		
	Offset Beam B7B8	Sqm	6	1	6.2	0.05		1.86		
	OffsetColumn B7B8	Sqm	6	6		0.05	3.3	5.94		
	Deduct									
	Door	Sqm	6	1/2	1.2		2.4	-8.64		
	Windows	Sqm	12	1/2	1.5		1.5	-13.50		
	Ventilator	Sqm	6	1/2	1.2		0.4	-1.44		
	Landscape	Sqm	1	2	6.75		3.3	44.55		
		Sqm	1	2	4.1		3.3	27.06		
	Offset Beam G7G8	Sqm	1	1	6.2	0.05		0.31		
	OffsetColumn G7G8	Sqm	1	2		0.05	3.3	0.33		
	Offset Beam H7H8	Sqm	1	1	6.2	0.05		0.31		
	OffsetColumn H7H8	Sqm	1	2		0.05	3.3	0.33		
	Offset Beam	Sqm	1	2	4.1	0.05		0.41		
	Offset Column	Sqm	1	2		0.05	3.3	0.33		
	Deduct	Sqm	1	2	0.2		0.45	-0.18		
	Door	Sqm	1	1/2	1.2		1.5	-0.90		
	Windows	Sqm	2	1/2	1.2		2.4	-2.88		
	Room 6&7									
	Long Wall A6 to C6	Sqm	2	1	6.82		3.3	45.01		
		Sqm	2	1	1.34		3.3	8.84		
	Long Wall A2 to C2	Sqm	2	1	2.1		3.3	13.86		
		Sqm	2	2	2.45		3.3	32.34		
		Sqm	2	1	4.15		3.3	27.39		
		Sqm	2	1	1.2		3.3	7.92		
	Beam	Sqm	2	2	1.3		1.1	5.72		
	Column A6 &M6	Sqm	2	1	1.4		2.92	8.18		
	Column Offset	Sqm	2	2	0.05		2.92	0.58		
	Deduct Beam	Sqm	2	4	0.2		0.45	-0.72		
	Short Wall A'2 to A'6	Sqm	2	1	6.15		3.3	40.59		
		Sqm	2	1	2.1		3.3	13.86		
	Short Wall C2 to C6	Sqm	2	1	2.6		3.3	17.16		
		Sqm	2	1	5.6		3.3	36.96		
	Beam	Sqm	2	1	1.5		1.1	3.30		
	Beam	Sqm	2	1	2.1		1.1	4.62		
	Deduct Beam	Sqm	2	4	0.2		0.45	-0.72		
	Column Offset	Sqm	2	4	0.05		2.92	1.17		
	Deduct									

Scanned with CamScanner

	Door	Sqm	2	1/2	1.2		2.4	-2.88		
	Windows	Sqm	8	1/2	1.8		1.5	-10.80		
	Passage									
		Sqm	1	1	40.46		3.3	133.52		
		Sqm	1	2	8.55		3.3	56.43		
		Sqm	1	2	6.57		3.3	43.36		
	Deduct W	Sqm	12	1/2	1.5		1.5	-13.50		
	Door	Sqm	1	1/2	1.2		2.4	-1.44		
	Entrance Lobby									
		Sqm	1	2	7.35		3.3	48.51		
	Stairs case									
	Stair case Area Below	Sqm	2	2	5.1		1.6	32.64		
		Sqm	2	1	3.4		1.6	10.88		
	Stair case Area Above	Sqm	2	2	5.1		1.3	26.52		
		Sqm	2	1	3.4		1.3	8.84		
	Column	Sqm	2	1	0.8		2.75	4.40		
	Deduct									
		Sqm	2	1/2	1.8		1.5	-2.70		
	Office 1 & 2 Short Wall	Sqm	2	1	6.17		3.3	40.72		
	D2 to F2 & L2 to M2	Sqm	2	2	2.48		3.3	32.74		
		Sqm	2	1	3.45		3.3	22.77		
	Column Offset	Sqm	2	4	0.05		2.92	1.17		
	Short Wall Long Wall	Sqm	2	1	5.06		3.3	33.40		
		Sqm	2	1	2.5		3.3	16.50		
		Sqm	2	1	3.3		3.3	21.78		
		Sqm	2	1	4.05		3.3	26.73		
	Column Offset	Sqm	2	2	0.05		2.92	0.58		
	Deduct		2					0.00		
	Door	Sqm	2	1/2	1.2		2.4	-2.88		
	Windows	Sqm	4	1/2	1.2		1.5	-3.60		
					Total Qty Work Done			1326.76		
					Upto 125%			1326.76	131.00	173805.56
62	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. - with primer									
		Sqm	1	1	1867.82			1867.82		
63	Providing and fixing **M.S. Hand railing for Balcony** with 50mm dia. M.S. hollow pipe of 14 gauge, welded to 20mmx20mm M.S. square rod placed vertically, spaced at 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. These assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections hould be cut to length, welded and grinded wherever necessary etc., complete . The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per									
	Stair Case G.F	Sqm	2	1	6.94		1	13.88		
	Stair Case F.F	Sqm	2	1	6.64		1	13.28		
	Stair Case S.F	Sqm	2	1	6.64		1	13.28		
	Stair Case T.F	Sqm	2	1	8.24		1	16.48		
	Conaction Slab First Floor Old PUC	Sqm	1	2	4.2		1.2	10.08		
	Conaction Slab First Floor Old Primary School	Sqm	1	2	3.5		1.2	8.40		
	Conaction Slab Second Slab Floor	Sqm	1	2	4.2		1.2	10.08		
	Conaction Slab First Floor Old Primary School	Sqm	1	2	3.5		1.2	8.40		

Scanned with CamScanner

					Total Qty Work Done			93.88			
					Upto 125%			55.00	3371.00	185405.00	
					Above 125%			38.88	3377.97	131335.64	
64	KSRB 7.5 : Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and ccessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM complete as per specifications. Shutter size										
		Nos	1	1	5.04			5.04			
65	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications. Clause 401 of MORTH V Revision. (pg no- 153,S Lno-20.5)KPWD S.R 2018-19										
		Sqm	1	1	68.37			68.37			
66	KSRB 14.6: Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. Specification No. KBS										
		Sqm	1	1	297.24			297.24			
67	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete.Page No. 27/ Item No. 5.29.2/										
		Nos	1	1	1100.89			1100.89			
68	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Page No. 180/ Item No. 24.1/ PWD SR 2018-19										
		Sqm	1	1	198.16			198.16			
69	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification I.No 10.5.1 P.No 69										
	First Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13			
	Second Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13			
	Third Floor Toilet Room	Sqm	2	1	6.75	2.75		37.13			
	Terrace	Sqm	1	1	43.60	16.92		737.71			
	Head Rooms	Sqm	2	1	3.60	4.16		29.95			
		Sqm	1	1	6.95	6.57		45.66			
	Deduct Head Rooms	Sqm	2	1	3.60	4.16		-29.95			
		Sqm	1	1	6.95	6.57		-45.66			
					Total Qty Work Done			894.75			
					Upto 125%			894.75	624.00	558523.06	
	WATER SUPPLY WORKS										

Scanned with CamScanner

70	Providing & fixing Chorinated Poly Venyl(CPVC) pipes confirming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling and testing of joints complete.(External work and Burried). Page No-99,Item No-13.87										
	25mm.dia..										
	Sump tank Motor	Mtr	2	3.50				7.00			
	Toilet	Mtr	8	6.75				54.00			
					Total Qty Work Done			61.00	212.00	12932.00	
71	32mm.dia..										
	Sump tank to water tank	Mtr	1	120.00				120.00			
		Mtr	2	13.00				26.00			
					Total Qty Work Done			146.00	268.00	39128.00	
72	40mm dia										
	Bore Well to Sump tank	Mtr	1	41				41.00			
					Total Qty Work Done			41.00	347.00	14227.00	
73	Providing and fixing water meter with stop cock, jam nut, socket in G.I pipe line including cutting and threading the pipe and making long screws including cost of all materials, labour , HOM of equipments and testing complete as per specifications.Page No-93,Item No-13.22										
		Set									
			1	6.00				6.00			
					Total Qty Work Done			6.00	1567.00	9402.00	
74	Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality below nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specification. Page No-94,Item No-13.42										
	a. 25mm.dia..	Each	1	12				12			
					Total Qty Work Done			12.00	609.00	7308.00	
75	Providing and fixing in position brass Gate valve with CI wheel of approved quality (screwed end) below nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specification. Page No-93,Item No-13.35										
		Nos	1	6.00				6.00	985.00	5910.00	
76	40mm.dia..										
		Nos	1	6.00				6.00	1234.00	7404.00	
77	KSRB13-7.1-3 : Providing and fixing in position 40mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.10 / 13.13 KSRB13-7.1-3 - do - 40 mm dia nominal bore Page No-95, Item No-13.54										
			1	6.00				11.00	1124.00	12364.00	
78	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 (Page No. 79, I.No. 12.5 of KPWD S.R 2018-19).										
	G. Floor Gents Toilet	Nos	1.00	5				5.00			
	G. Floor Ladies Toilet	Nos	1.00	5				5.00			
	F. Floor Gents Toilet	Nos	1.00	5				5.00			
	F.Floor Ladies Toilet	Nos	1.00	5				5.00			
	S.Floor Gents Toilet	Nos	1.00	5				5.00			
	S.Floor Ladies Toilet	Nos	1.00	5				5.00			
	T.Floor Gents Toilet	Nos	1.00	5				5.00			
	T.Floor Ladies Toilet	Nos	1.00	5				5.00			
					Total Qty Work Done			40.00			
					Upto 125%			40.00	5882.00	235280.00	

Scanned with CamScanner

79	Providing and fixing white vitreous china clay, angle back wash basin size 600X480mm with a single 15mm C.P brass pillar tap with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications										
	G. Floor Gents Toilet	Nos	1.00	3				3.00			
	G. Floor Ladies Toilet	Nos	1.00	5				5.00			
	F. Floor Gents Toilet	Nos	1.00	3				3.00			
	F. Floor Ladies Toilet	Nos	1.00	5				5.00			
	S.Floor Gents Toilet	Nos	1.00	3				3.00			
	S.Floor Ladies Toilet	Nos	1.00	5				5.00			
	T.Floor Gents Toilet	Nos	1.00	3				3.00			
	T.Floor Ladies Toilet	Nos	1.00	5				5.00			
						Total Qty Work Done		32.00			
						Upto 125%		23.00	3903.00	89769.00	
						Above 125%		9.00	3902.59	35123.34	
80	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials labour and HOM with all leads complete as per specifications. Specification No KBS 13 2.2										
	G. Floor Gents Toilet	Nos	1.00	13				13.00			
	G. Floor Ladies Toilet	Nos	1.00	10				10.00			
	F. Floor Gents Toilet	Nos	1.00	13				13.00			
	F. Floor Ladies Toilet	Nos	1.00	10				10.00			
	S.Floor Gents Toilet	Nos	1.00	13				13.00			
	S.Floor Ladies Toilet	Nos	1.00	10				10.00			
	T.Floor Gents Toilet	Nos	1.00	13				13.00			
	T.Floor Ladies Toilet	Nos	1.00	10				10.00			
						Total Qty Work Done		92.00			
						Upto 125%		50.00	226.00	11300.00	
						Above 125%		42.00	225.51	9471.62	
81	Providing and fixing C.P. brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications.										
		Nos	1	1	16			16.00			
82	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. 20mm nominal OD pipes (KPWD SR 2018-19, P-99, It-13.87.6)										
	Ground Floor										
	Ladies toilet for wash basin	Rmt	1	1	4.25			4.25			
	Ladies toilet for flush tank	Rmt	5	1	0.20			1.00			
	Ladies toilet for bib cock	Rmt	5	1	0.95			4.75			
	Ladies toilet for bib cock	Rmt	5	1	0.75			3.75			
	Gents toilet for wash basin And Urinals	Rmt	1	1	9.50			9.50			
	Gents toilet for bib cock	Rmt	5	1	0.95			4.75			
	Gentstoilet for flush tank	Rmt	5	1	0.20			1.00			
	First Floor										
	Ladies toilet for wash basin	Rmt	1	1	4.25			4.25			
	Ladies toilet for flush tank	Rmt	5	1	0.20			1.00			
	Ladies toilet for bib cock	Rmt	5	1	0.95			4.75			
	Ladies toilet for bib cock	Rmt	5	1	0.75			3.75			
	Gents toilet for wash basin And Urinals	Rmt	1	1	9.50			9.50			
	Gents toilet for bib cock	Rmt	5	1	0.95			4.75			
	Gentstoilet for flush tank	Rmt	5	1	0.20			1.00			

Scanned with CamScanner

	Second Floor									
	Ladies toilet for wash basin	Rmt	1	1	4.25			4.25		
	Ladies toilet for flush tank	Rmt	5	1	0.20			1.00		
	Ladies toilet for bib cock	Rmt	5	1	0.95			4.75		
	Ladies toilet for bib cock	Rmt	5	1	0.75			3.75		
	Gents toilet for wash basin And Urinals	Rmt	1	1	9.50			9.50		
	Gents toilet for bib cock	Rmt	5	1	0.95			4.75		
	Gentstoilet for flush tank	Rmt	5	1	0.20			1.00		
	Third Floor									
	Ladies toilet for wash basin	Rmt	1	1	4.25			4.25		
	Ladies toilet for flush tank	Rmt	5	1	0.20			1.00		
	Ladies toilet for bib cock	Rmt	5	1	0.95			4.75		
	Ladies toilet for bib cock	Rmt	5	1	0.75			3.75		
	Gents toilet for wash basin And Urinals	Rmt	1	1	9.50			9.50		
	Gents toilet for bib cock	Rmt	5	1	0.95			4.75		
	Gentstoilet for flush tank	Rmt	5	1	0.20			1.00		
					Total Qty Work Done			116.00	245.00	28420.00
83	Providing & fixing Chorinated Poly Venyl(CPVC)20mm nominal OD pipes confirming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of jionts complete. trenching, refilling and testing of joints complete.(Concealed work including cutting									
		Mtr	1	1	500			500		
84	Providing & fixing Chorinated Poly Venyl(CPVC)20mm nominal OD pipes confirming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of jionts complete. trenching, refilling and testing of joints complete.(Concealed work including cutting									
		Mtr	1	1	510			510		
85	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3									
			1.00	6				6.00		
					Total Qty Work Done			6.00	167.00	1002.00
86	Providing and fixing in position brass stop cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM with all leads complete as per specifications. Specification No.KBS 13.2.2									
	G. Floor Gents Toilet	Mtr	1.00	13				13.00		
	G. Floor Ladies Toilet	Mtr	1.00	10				10.00		
	F. Floor Gents Toilet	Mtr	1.00	13				13.00		
	F.Floor Ladies Toilet	Mtr	1.00	10				10.00		
	S.Floor Gents Toilet	Mtr	1.00	13				13.00		
	S.Floor Ladies Toilet	Mtr	1.00	10				10.00		
	T.Floor Gents Toilet	Mtr	1.00	13				13.00		
	T.Floor Ladies Toilet	Mtr	1.00	10				10.00		
					Total Qty Work Done			92.00		
					Upto 125%			15.00	167.00	2505.00
					Above 125%			77.00	167.36	12886.39
87	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 for internal water supply									
		Mtr	1	1	450			450		

Scanned with CamScanner

88	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 for internal water supply connection. 75mm dia										
	G. Floor Gents Toilet Internal	Mtr	1.00	7.00				7.00			
	G. Floor Ladies Toilet Internal	Mtr	1.00	7.00				7.00			
	F.Floor Gents Toilet Internal	Mtr	1.00	7.00				7.00			
	F.Floor Ladies Toilet Internal	Mtr	1.00	7.00				7.00			
	S.Floor Gents Toilet Internal	Mtr	1.00	7.00				7.00			
	S.Floor Ladies Toilet Internal	Mtr	1.00	7.00				7.00			
	T.Floor Gents Toilet Internal	Mtr	1.00	7.00				7.00			
	T.Floor Ladies Toilet Internal	Mtr	1.00	7.00				7.00			
					Total Qty Work Done			56.00	387.00	21672.00	
89	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure of outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9 for internal water supply										
	A'8 to N'8 Back Side	Mtr	1	8.00	14.2			113.6			
		Mtr	2	5.00	14.2			142.00			
	Gents Toilet External	Mtr	1	1.00	10.65			10.65			
	Ladies Toilet External	Mtr	1	1.00	10.65			10.65			
	Toilet to Chamber External	Mtr	1	1.00	2.75			2.75			
	Toilet to Chamber External	Mtr	1	1.00	1.10			1.10			
	Gents Toilet External	Mtr	4	5.00	10.65			213.00			
	Ladies Toilet External	Mtr	4	5.00	10.65			213.00			
	Gents Toilet Internal	Mtr	4	5.00	0.35			7.00			
	Ladies Toilet Internal	Mtr	4	5.00	0.35			7.00			
					Total Qty Work Done			720.75			
					Upto 125%			250.00	534.00	133500.00	
					Above 125%			470.75	706.22	332451.84	
90	Constructing brick masonry inspection chamber for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 600x600mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 600x600mm										
	Gents Toilet	1.00	8					8.00			
	Ladies Toilet	1.00	12					12.00			
					Total Qty Work Done			20.00			
					Upto 125%			20.00	10077.00	201540.00	
	ELECTRICAL WORK SR 2019-20										
91	Supplying heavy gauge PVC conduit pipe .....mm dia ..... mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire										
	S.F 19/20mm dia 2mm thick	Mtr	1	440				440.00			
	T.F 19/20mm dia 2mm thick.	Mtr	1	440				440.00			
	H.Room 19/20mm dia 2mm	Mtr	1	120				120.00			
					Total Qty Work Done			1000.00			
					Upto 125%			1000.00	44	44000.00	

Scanned with CamScanner

92	Supplying heavy gauge PVC conduit pipe .....mm dia ..... mm thick confirming to IS 2509 with suitable size bends, metal/PVC junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire										
	S.F 25mm dia 2mm thick.	Mtr	1	260				260.00			
	T.F 25mm dia 2mm thick.	Mtr	1	260				260.00			
	H.Room 25mm dia 2mm thic	Mtr	1	80				80.00			
					Total Qty Work Done			600.00			
					Upto 125%			600.00	58	34800.00	
93	32mm dia 2.5mm thick										
		Mtr	1	1	300			300			
94	Groove cutting in walls Supplying heavy gauge PVC Conduit Pipe ....dia ....mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary.										
	S.F 19/20mm dia 2mm thick	Mtr	1	170				170.00			
	T.F 19/20mm dia 2mm thick	Mtr	1	170				170.00			
	H.Room 19/20mm dia 2mm t	Mtr	1	55				55.00			
					Total Qty Work Done			395.00			
					Upto 125%			395.00	56.00	22120.00	
95	Groove cutting in walls Supplying heavy gauge PVC Conduit Pipe ....dia ....mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary.										
	S.F 25mm dia 2mm thick.	Mtr	1	95				95.00			
	T.F 25mm dia 2mm thick.	Mtr	1	95				95.00			
	H.Room 25mm dia 2mm thic	Mtr	1	35				35.00			
					Total Qty Work Done			225.00	59.00	13275.00	
96	32mm dia 2.5mm thick.										
		Mtr	1	1	165			165			
97	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete.										
		Mtr	1	1	175			175			
98	Upto 50mm Conduit CC floor										
		Mtr	1	1	115			115			
99	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm .... etc. as required.25mm										
		Mtr	1	1	310			310			
100	Supplying And Fixing Metal Fan Box with Round Hook										
	Second Floor	Nos	1	13				13.00			
	Third Floor	Nos	1	13				13.00			
					Total Qty Work Done			26.00			
					Upto 125%			8.00	93.00	744.00	
					Above 125%			18.00	93.42	1681.47	
	PART-B WIRES & CABLES										
101	Point wiring using Copper wire without switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A										
	Ground floor										
	Toilet (class room)	No	1	1.00				1.00			
	Class room 1	No	1	1.00				1.00			
	Class room 2	No	1	1.00				1.00			
	Class room 3	No	1	1.00				1.00			
	Class room 4	No	1	1.00				1.00			

Scanned with CamScanner

	Class room 5	No	1	1.00				1.00			
	Class room 6	No	1	1.00				1.00			
	Class room 7	No	1	1.00				1.00			
	First floor										
	Toilet (class room)	No	1	1.00				1.00			
	Class room 1	No	1	1.00				1.00			
	Class room 2	No	1	1.00				1.00			
	Class room 3	No	1	1.00				1.00			
	Class room 4	No	1	1.00				1.00			
	Class room 5	No	1	1.00				1.00			
	Class room 6	No	1	1.00				1.00			
	Class room 7	No	1	1.00				1.00			
	Second floor	No									
	Toilet (class room)	No	1	1.00				1.00			
	Class room 1	No	1	1.00				1.00			
	Class room 2	No	1	1.00				1.00			
	Class room 3	No	1	1.00				1.00			
	Class room 4	No	1	1.00				1.00			
	Class room 5	No	1	1.00				1.00			
	Class room 6	No	1	1.00				1.00			
	Class room 7	No	1	1.00				1.00			
	Third floor	No									
	Toilet (class room)	No	1	1.00				1.00			
	Class room 1	No	1	1.00				1.00			
	Class room 2	No	1	1.00				1.00			
	Class room 3	No	1	1.00				1.00			
	Class room 4	No	1	1.00				1.00			
	Class room 5	No	1	1.00				1.00			
	Class room 6	No	1	1.00				1.00			
	Class room 7	No	1	1.00				1.00			
	Fourth floor										
	Class room 1	No	1	1.00				1.00			
							Total Qty Work Done	33.00		176	5808.00
102	Medium point 3 Mtr to 6 Mtrfrom tapping point to out let via switch										
	Ground Floor										
	Office 1 & 2	No	1	4				4.00			
	Toilet (class room)	No	1	4				4.00			
	Class room 1	No	1	2				2.00			
	Class room 2	No	1	2				2.00			
	Class room 3	No	1	2				2.00			
	Class room 4	No	1	2				2.00			
	Class room 5	No	1	2				2.00			
	Class room 6	No	1	2				2.00			
	Class room 7	No	1	2				2.00			
	First floor							0.00			
	Office 1 & 2	No	1	4				4.00			
	Toilet (class room)	No	1	4				4.00			
	Class room 1	No	1	2				2.00			
	Class room 2	No	1	2				2.00			
	Class room 3	No	1	2				2.00			
	Class room 4	No	1	2				2.00			
	Class room 5	No	1	2				2.00			
	Class room 6	No	1	2				2.00			
	Class room 7	No	1	2				2.00			
	Second floor							0.00			
	Office 1 & 2	No	1	4				4.00			
	Toilet (class room)	No	1	4				4.00			
	Class room 1	No	1	2				2.00			

Scanned with CamScanner

	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Third floor							0.00		
	Office 1 & 2	No	1	4				4.00		
	Toilet (class room)	No	1	4				4.00		
	Class room 1	No	1	2				2.00		
	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Fourth floor	No						0.00		
	Head Room	No	1	2				2.00		
						Total Qty Work Done		90.00		
						Upto 125%		40	275	24750.00
						Above 125%		50.00	274.75	10990.00
103	Point wiring using Copper wire without switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A - Two outlet in a row, above 6Mtr upto 10Mtr from tapping point to out let via switches ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.									
	Ground floor									
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	12				12.00		
	Class room 1	No	1	10				10.00		
	Class room 2	No	1	10				10.00		
	Class room 3	No	1	10				10.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	10				10.00		
	Class room 5	No	1	10				10.00		
	Class room 6	No	1	10				10.00		
	Class room 7	No	1	10				10.00		
	Corridor	No	1	1				1.00		
	First floor	No	1					0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	12				12.00		
	Class room 1	No	1	10				10.00		
	Class room 2	No	1	10				10.00		
	Class room 3	No	1	10				10.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	10				10.00		
	Class room 5	No	1	10				10.00		
	Class room 6	No	1	10				10.00		
	Class room 7	No	1	10				10.00		
	Corridor	No	1	1				1.00		
	Second floor	No	1					0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	12				12.00		
	Class room 1	No	1	10				10.00		
	Class room 2	No	1	10				10.00		
	Class room 3	No	1	10				10.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	10				10.00		
	Class room 5	No	1	10				10.00		

Scanned with CamScanner

	Class room 6	No	1	10				10.00		
	Class room 7	No	1	10				10.00		
	Corridor	No	1	1				1.00		
	Third floor	No	1					0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	12				12.00		
	Class room 1	No	1	10				10.00		
	Class room 2	No	1	10				10.00		
	Class room 3	No	1	10				10.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	10				10.00		
	Class room 5	No	1	10				10.00		
	Class room 6	No	1	10				10.00		
	Class room 7	No	1	10				10.00		
	Corridor	No	1	1				1.00		
	Fourth floor	No	1					0.00		
	Head Room	No	1	10				10.00		
	Staircase	No	1	2				2.00		
							Total Qty Work Done	400.00		
							Upto 125%	25.00	412	10300.00
							Above 125%	375.00	412	154500.00
104	Point wiring using Copper wire without switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A - Two outlet in a row, above 3Mtr upto 6Mtr from tapping point to out let via switches ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.										
	Ground floor										
	Corridor	Point	1	10				10.00		
	First floor										
	Corridor	Point	1	10				10.00		
	Second floor										
	Corridor	Point	1	10				10.00		
	Third floor										
	Corridor	Point	1	10				10.00		
							Total Qty Work Done	40.00	522	20880.00
105	There outlet in a row, above 6Mtr upto 10Mtr from tapping point to out let via switches									
		Point	1	1	48			48		
106	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A - 1.5 sqmm ---- etc , complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.2.3.2 Page 5)									
	Ground Floor									
	DB to Office PP 1	Mtr	1	49.00				49.00		
	DB to Office SB 1	Mtr	1	48.50				48.50		
	Office SB 1 to SB 1A	Mtr	1	15.00				15.00		
	DB to Office PP 2	Mtr	1	43.00				43.00		
	DB to Office SB 2	Mtr	1	42.50				42.50		
	Office SB 2 to SB 2A	Mtr	1	15.00				15.00		
	DB to Class room SB	Mtr	1	34.50				34.50		
	Class room SB 1 (toilet) to	Mtr	1	12.00				12.00		
	Class room SB 1 (toilet) to	Mtr	1	12.50				12.50		
	DB to Class room 1 SB 1	Mtr	1	28.50				28.50		
	Class room 1 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 1 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 2 SB 1	Mtr	1	21.50				21.50		
	Class room 2 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 2 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 3 SB 1	Mtr	1	12.50				12.50		
	Class room 3 SB 1 to SB 2	Mtr	1	14.50				14.50		

Scanned with CamScanner

	Class room 3 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Staircase SB 1	Mtr	1	10.50				10.50		
	Staircase SB 1to SB 2	Mtr	1	10.50				10.50		
	DB to Class room 4 SB 1	Mtr	1	10.50				10.50		
	Class room 4 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 4 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 5 SB 1	Mtr	1	14.50				14.50		
	Class room 5 SB 1 to SB 2	Mtr	1	16.00				16.00		
	Class room 5 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 6 SB 1	Mtr	1	24.50				24.50		
	Class room 6 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 6 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 7 SB 1	Mtr	1	31.50				31.50		
	Class room 7 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 7 SB 1 to SB 3	Mtr	1	16.00				16.00		
	First Floor							0.00		
	DB to Office PP 1	Mtr	1	49.00				49.00		
	DB to Office SB 1	Mtr	1	48.50				48.50		
	Office SB 1 to SB 1A	Mtr	1	15.00				15.00		
	DB to Office PP 2	Mtr	1	43.00				43.00		
	DB to Office SB 2	Mtr	1	42.50				42.50		
	Office SB 2 to SB 2A	Mtr	1	15.00				15.00		
	DB to Class room SB	Mtr	1	34.50				34.50		
	Class room SB 1 (toilet) to	Mtr	1	12.00				12.00		
	Class room SB 1 (toilet) to	Mtr	1	12.50				12.50		
	DB to Class room 1 SB 1	Mtr	1	28.50				28.50		
	Class room 1 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 1 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 2 SB 1	Mtr	1	21.50				21.50		
	Class room 2 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 2 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 3 SB 1	Mtr	1	12.50				12.50		
	Class room 3 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 3 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Staircase SB 1	Mtr	1	10.50				10.50		
	Staircase SB 1to SB 2	Mtr	1	10.50				10.50		
	DB to Class room 4 SB 1	Mtr	1	10.50				10.50		
	Class room 4 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 4 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 5 SB 1	Mtr	1	14.50				14.50		
	Class room 5 SB 1 to SB 2	Mtr	1	16.00				16.00		
	Class room 5 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 6 SB 1	Mtr	1	24.50				24.50		
	Class room 6 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 6 SB 1 to SB 3	Mtr	1	16.00				16.00		
	DB to Class room 7 SB 1	Mtr	1	31.50				31.50		
	Class room 7 SB 1 to SB 2	Mtr	1	14.50				14.50		
	Class room 7 SB 1 to SB 3	Mtr	1	16.00				16.00		
	Second Floor							0.00		
	DB to Office PP 1	Mtr	1	49.00				49.00		
	DB to Office SB 1	Mtr	1	48.50				48.50		
	Office SB 1 to SB 1A	Mtr	1	15.00				15.00		
	DB to Office PP 2	Mtr	1	43.00				43.00		
	DB to Office SB 2	Mtr	1	42.50				42.50		
	Office SB 2 to SB 2A	Mtr	1	15.00				15.00		
	DB to Class room SB	Mtr	1	34.50				34.50		
	Class room SB 1 (toilet) to	Mtr	1	12.00				12.00		
	Class room SB 1 (toilet) to	Mtr	1	12.50				12.50		
	DB to Class room 1 SB 1	Mtr	1	28.50				28.50		

Scanned with CamScanner

	Class room 1 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 1 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 2 SB 1	Mtr	1	21.50				21.50			
	Class room 2 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 2 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 3 SB 1	Mtr	1	12.50				12.50			
	Class room 3 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 3 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Staircase SB 1	Mtr	1	10.50				10.50			
	Staircase SB 1to SB 2	Mtr	1	10.50				10.50			
	DB to Class room 4 SB 1	Mtr	1	10.50				10.50			
	Class room 4 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 4 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 5 SB 1	Mtr	1	14.50				14.50			
	Class room 5 SB 1 to SB 2	Mtr	1	16.00				16.00			
	Class room 5 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 6 SB 1	Mtr	1	24.50				24.50			
	Class room 6 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 6 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 7 SB 1	Mtr	1	31.50				31.50			
	Class room 7 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 7 SB 1 to SB 3	Mtr	1	16.00				16.00			
	Third Floor							0.00			
	DB to Office PP 1	Mtr	1	49.00				49.00			
	DB to Office SB 1	Mtr	1	48.50				48.50			
	Office SB 1 to SB 1A	Mtr	1	15.00				15.00			
	DB to Office PP 2	Mtr	1	43.00				43.00			
	DB to Office SB 2	Mtr	1	42.50				42.50			
	Office SB 2 to SB 2A	Mtr	1	15.00				15.00			
	DB to Class room SB	Mtr	1	34.50				34.50			
	Class room SB 1 (toilet) to	Mtr	1	12.00				12.00			
	Class room SB 1 (toilet) to	Mtr	1	12.50				12.50			
	DB to Class room 1 SB 1	Mtr	1	28.50				28.50			
	Class room 1 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 1 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 2 SB 1	Mtr	1	21.50				21.50			
	Class room 2 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 2 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 3 SB 1	Mtr	1	12.50				12.50			
	Class room 3 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 3 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Staircase SB 1	Mtr	1	10.50				10.50			
	Staircase SB 1to SB 2	Mtr	1	10.50				10.50			
	DB to Class room 4 SB 1	Mtr	1	10.50				10.50			
	Class room 4 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 4 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 5 SB 1	Mtr	1	14.50				14.50			
	Class room 5 SB 1 to SB 2	Mtr	1	16.00				16.00			
	Class room 5 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 6 SB 1	Mtr	1	24.50				24.50			
	Class room 6 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 6 SB 1 to SB 3	Mtr	1	16.00				16.00			
	DB to Class room 7 SB 1	Mtr	1	31.50				31.50			
	Class room 7 SB 1 to SB 2	Mtr	1	14.50				14.50			
	Class room 7 SB 1 to SB 3	Mtr	1	16.00				16.00			
	Fourth Floor										
	DB to Staircase SB 1	Mtr	1	10.50				10.50			
	Staircase SB 1to SB 2	Mtr	1	10.50				10.50			
	DB to Head Room SB 1	Mtr	1	31.50				31.50			

Scanned with CamScanner

	Head Room SB 1 to SB 2	Mtr	1	14.50				14.50		
	Head Room SB 1 to SB 3	Mtr	1	16.00				16.00		
					Total Qty Work Done			2689.00		
					Upto 125%			2689.00	23	61847.00
107	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A, - 2.5 sqmm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.2.3.3 Page 6)									
	Ground Floor									
	DB to Office SB 1	Mtr	2	48.50				97.00		
	Office SB 1 to SB 1A	Mtr	2	15.00				30.00		
	DB to Office SB 2	Mtr	2	42.50				85.00		
	Office SB 2 to SB 2A	Mtr	2	15.00				30.00		
	DB to Class room SB	Mtr	2	34.50				69.00		
	Class room SB 1 (toilet) to	Mtr	2	12.00				24.00		
	Class room SB 1 (toilet) to	Mtr	2	12.50				25.00		
	DB to Class room 1 SB 1	Mtr	2	28.50				57.00		
	Class room 1 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 1 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 2 SB 1	Mtr	2	21.50				43.00		
	Class room 2 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 2 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 3 SB 1	Mtr	2	12.50				25.00		
	Class room 3 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 3 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Staircase SB 1	Mtr	2	10.50				21.00		
	Staircase SB 1to SB 2	Mtr	2	10.50				21.00		
	DB to Class room 4 SB 1	Mtr	2	10.50				21.00		
	Class room 4 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 4 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 5 SB 1	Mtr	2	14.50				29.00		
	Class room 5 SB 1 to SB 2	Mtr	2	16.00				32.00		
	Class room 5 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 6 SB 1	Mtr	2	24.50				49.00		
	Class room 6 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 6 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 7 SB 1	Mtr	2	31.50				63.00		
	Class room 7 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 7 SB 1 to SB 3	Mtr	2	16.00				32.00		
	First Floor									
	DB to Office SB 1	Mtr	2	48.50				97.00		
	Office SB 1 to SB 1A	Mtr	2	15.00				30.00		
	DB to Office SB 2	Mtr	2	42.50				85.00		
	Office SB 2 to SB 2A	Mtr	2	15.00				30.00		
	DB to Class room SB	Mtr	2	34.50				69.00		
	Class room SB 1 (toilet) to	Mtr	2	12.00				24.00		
	Class room SB 1 (toilet) to	Mtr	2	12.50				25.00		
	DB to Class room 1 SB 1	Mtr	2	28.50				57.00		
	Class room 1 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 1 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 2 SB 1	Mtr	2	21.50				43.00		
	Class room 2 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 2 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 3 SB 1	Mtr	2	12.50				25.00		
	Class room 3 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 3 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Staircase SB 1	Mtr	2	10.50				21.00		
	Staircase SB 1to SB 2	Mtr	2	10.50				21.00		

Scanned with CamScanner

	DB to Class room 4 SB 1	Mtr	2	10.50				21.00		
	Class room 4 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 4 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 5 SB 1	Mtr	2	14.50				29.00		
	Class room 5 SB 1 to SB 2	Mtr	2	16.00				32.00		
	Class room 5 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 6 SB 1	Mtr	2	24.50				49.00		
	Class room 6 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 6 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 7 SB 1	Mtr	2	31.50				63.00		
	Class room 7 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 7 SB 1 to SB 3	Mtr	2	16.00				32.00		
	Second Floor									
	DB to Office SB 1	Mtr	2	48.50				97.00		
	Office SB 1 to SB 1A	Mtr	2	15.00				30.00		
	DB to Office SB 2	Mtr	2	42.50				85.00		
	Office SB 2 to SB 2A	Mtr	2	15.00				30.00		
	DB to Class room SB	Mtr	2	34.50				69.00		
	Class room SB 1 (toilet) to	Mtr	2	12.00				24.00		
	Class room SB 1 (toilet) to	Mtr	2	12.50				25.00		
	DB to Class room 1 SB 1	Mtr	2	28.50				57.00		
	Class room 1 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 1 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 2 SB 1	Mtr	2	21.50				43.00		
	Class room 2 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 2 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 3 SB 1	Mtr	2	12.50				25.00		
	Class room 3 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 3 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Staircase SB 1	Mtr	2	10.50				21.00		
	Staircase SB 1to SB 2	Mtr	2	10.50				21.00		
	DB to Class room 4 SB 1	Mtr	2	10.50				21.00		
	Class room 4 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 4 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 5 SB 1	Mtr	2	14.50				29.00		
	Class room 5 SB 1 to SB 2	Mtr	2	16.00				32.00		
	Class room 5 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 6 SB 1	Mtr	2	24.50				49.00		
	Class room 6 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 6 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 7 SB 1	Mtr	2	31.50				63.00		
	Class room 7 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 7 SB 1 to SB 3	Mtr	2	16.00				32.00		
	Third Floor									
	DB to Office SB 1	Mtr	2	48.50				97.00		
	Office SB 1 to SB 1A	Mtr	2	15.00				30.00		
	DB to Office SB 2	Mtr	2	42.50				85.00		
	Office SB 2 to SB 2A	Mtr	2	15.00				30.00		
	DB to Class room SB	Mtr	2	34.50				69.00		
	Class room SB 1 (toilet) to	Mtr	2	12.00				24.00		
	Class room SB 1 (toilet) to	Mtr	2	12.50				25.00		
	DB to Class room 1 SB 1	Mtr	2	28.50				57.00		
	Class room 1 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 1 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 2 SB 1	Mtr	2	21.50				43.00		
	Class room 2 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 2 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 3 SB 1	Mtr	2	12.50				25.00		
	Class room 3 SB 1 to SB 2	Mtr	2	14.50				29.00		

Scanned with CamScanner

	Class room 3 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Staircase SB 1	Mtr	2	10.50				21.00		
	Staircase SB 1to SB 2	Mtr	2	10.50				21.00		
	DB to Class room 4 SB 1	Mtr	2	10.50				21.00		
	Class room 4 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 4 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 5 SB 1	Mtr	2	14.50				29.00		
	Class room 5 SB 1 to SB 2	Mtr	2	16.00				32.00		
	Class room 5 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 6 SB 1	Mtr	2	24.50				49.00		
	Class room 6 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 6 SB 1 to SB 3	Mtr	2	16.00				32.00		
	DB to Class room 7 SB 1	Mtr	2	31.50				63.00		
	Class room 7 SB 1 to SB 2	Mtr	2	14.50				29.00		
	Class room 7 SB 1 to SB 3	Mtr	2	16.00				32.00		
	Fourth Floor									
	DB to Staircase SB 1	Mtr	2	10.50				21.00		
	Staircase SB 1to SB 2	Mtr	2	10.50				21.00		
	DB to Head Room SB 1	Mtr	2	31.50				63.00		
	Head Room SB 1 to SB 2	Mtr	2	14.50				29.00		
	Head Room SB 1 to SB 3	Mtr	2	16.00				32.00		
						Total Qty Work Done		4642.00		
						Upto 125%		4642.00	34	157828.00
108	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A. - 4 sqmm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.2.3.4 Page 6)									
	Ground Floor									
	DB to Office PP 1	Mtr	2	49.00				98.00		
	DB to Office PP 2	Mtr	2	43.00				86.00		
	First Floor									
	DB to Office PP 1	Mtr	2	49.00				98.00		
	DB to Office PP 2	Mtr	2	43.00				86.00		
	Meter board to MCBDB	Mtr	2	10.00				20.00		
	Second Floor									
	DB to Office PP 1	Mtr	2	49.00				98.00		
	DB to Office PP 2	Mtr	2	43.00				86.00		
	Meter board to MCBDB	Mtr	2	10.00				20.00		
	Third Floor									
	DB to Office PP 1	Mtr	2	49.00				98.00		
	DB to Office PP 2	Mtr	2	43.00				86.00		
	Meter board to MCBDB	Mtr	2	10.00				20.00		
	Fourth Floor									
	Meter board to MCBDB	Mtr	2	10.00				20.00		
						Total Qty Work Done		816.00	47	38352.00
109	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A. - 6 sqmm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.2.3.3 Page 6)									
	Meter board to MCBDBs Ground floor	Mtr	4	12.00				48.00		
			4	17.00				68.00		
	Meter board to MCBDBs First floor	Mtr	4	16.00				64.00		
			4	21.00				84.00		
	Meter board to MCBDBs Second floor	Mtr	4	20.00				80.00		
			4	25.00				100.00		
	Meter board to MCBDBs Third floor	Mtr	4	24.00				96.00		

Scanned with CamScanner

	Meter board to MCBDBs		4	29.00				116.00		
	Fourth floor	Mtr	4	28.00				112.00		
			4	33.00				132.00		
						Total Qty Work Done		900.00	74	66600.00
110	10Sqmm									
		Mtr	1	1	370			370		
111	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C C wall - 1-3Way ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.									
	Ground floor									
	Office 1 & 2	Each	1	4				4.00		
	Staircase	Each	1	1				1.00		
	First floor							0.00		
	Office 1 & 2	Each	1	4				4.00		
	Staircase	Each	1	1				1.00		
	Second floor							0.00		
	Office 1 & 2	Each	1	4				4.00		
	Staircase	Each	1	1				1.00		
	Third floor							0.00		
	Office 1 & 2	Each	1	4				4.00		
	Staircase	Each	1	1				1.00		
	Fourth floor							0.00		
	Office 1 & 2	Each	1	1				1.00		
						Total Qty Work Done		21.00	104	2184.00
112	4-5way									
		Nos	1	1.00	42			42.00		
113	6Way									
		Nos	1	1.00	51			51.00		
114	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall - 8Way ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No. 3.4.4 P 9)									
	Ground floor									
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				2.00		
	First floor	Nos						0.00		
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				2.00		
	Second floor	Nos						0.00		
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		

Scanned with CamScanner

	Class room 3	Nos	1	1				1.00			
	Staircase	Nos	1	1				1.00			
	Class room 4	Nos	1	1				1.00			
	Class room 5	Nos	1	1				1.00			
	Class room 6	Nos	1	1				1.00			
	Class room 7	Nos	1	1				2.00			
	Corridor	Nos	1	2				0.00			
	Third floor	Nos						1.00			
	Toilet (class room)	Nos	1	1				1.00			
	Class room 1	Nos	1	1				1.00			
	Class room 2	Nos	1	1				1.00			
	Class room 3	Nos	1	1				1.00			
	Staircase	Nos	1	1				1.00			
	Class room 4	Nos	1	1				1.00			
	Class room 5	Nos	1	1				1.00			
	Class room 6	Nos	1	1				1.00			
	Class room 7	Nos	1	1				2.00			
	Corridor	Nos	1	2				0.00			
	Fourth floor	Nos						1.00			
	Head Room	Nos	1	1				45.00			
						Total Qty Work Done		36		159	5724.00
						Upto 125%		9.00		159.36	1434.20
						Above 125%					
115	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall - 10-12Way ---- etc . complete with all lead & lift, as per specifications and as per directions of the										
	Ground floor										
	Office 1 & 2	Nos	1	8				8.00			
	Toilet (class room)	Nos	1	2				2.00			
	Class room 1	Nos	1	2				2.00			
	Class room 2	Nos	1	2				2.00			
	Class room 3	Nos	1	2				2.00			
	Class room 4	Nos	1	2				2.00			
	Class room 5	Nos	1	2				2.00			
	Class room 6	Nos	1	2				2.00			
	Class room 7	Nos	1	2				2.00			
	First floor	Nos						0.00			
	Office 1 & 2	Nos	1	8				8.00			
	Toilet (class room)	Nos	1	2				2.00			
	Class room 1	Nos	1	2				2.00			
	Class room 2	Nos	1	2				2.00			
	Class room 3	Nos	1	2				2.00			
	Staircase	Nos						0.00			
	Class room 4	Nos	1	2				2.00			
	Class room 5	Nos	1	2				2.00			
	Class room 6	Nos	1	2				2.00			
	Class room 7	Nos	1	2				2.00			
	Second floor	Nos						0.00			
	Office 1 & 2	Nos	1	8				8.00			
	Toilet (class room)	Nos	1	2				2.00			
	Class room 1	Nos	1	2				2.00			
	Class room 2	Nos	1	2				2.00			
	Class room 3	Nos	1	2				2.00			
	Class room 4	Nos	1	2				2.00			
	Class room 5	Nos	1	2				2.00			
	Class room 6	Nos	1	2				2.00			
	Class room 7	Nos	1	2				2.00			
	Third floor	Nos						0.00			

Scanned with CamScanner

	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	2				2.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Staircase	Nos	1					0.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Fourth floor	Nos						0.00		
	Head Room	Nos	1	2				2.00		
					Total Qty Work Done			98.00		
					Upto 125%			20	181	3620.00
					Above 125%			78.00	181	14118.00
116	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. - 1 to 3 Module (Item No.3.5.4 P 9)									
		Nos	1	1	20			20		
117	4 Module									
		Nos	1	1	20			20		
118	6 Module									
		Nos	1	1	20			20		
119	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. - 8 Module ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.									
	Ground floor									
	Office 1 & 2	Nos								
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				2.00		
	First floor	Nos	1					0.00		
	Office 1 & 2	Nos	1					0.00		
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				1.00		
	Second floor	Nos	1					2.00		
	Office 1 & 2	Nos	1					0.00		
	Toilet (class room)	Nos	1	1				0.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				1.00		
	Third floor	Nos	1					2.00		
								0.00		

Scanned with CamScanner

	Office 1 & 2	Nos	1					0.00		
	Toilet (class room)	Nos	1	1				1.00		
	Class room 1	Nos	1	1				1.00		
	Class room 2	Nos	1	1				1.00		
	Class room 3	Nos	1	1				1.00		
	Staircase	Nos	1	1				1.00		
	Class room 4	Nos	1	1				1.00		
	Class room 5	Nos	1	1				1.00		
	Class room 6	Nos	1	1				1.00		
	Class room 7	Nos	1	1				1.00		
	Corridor	Nos	1	2				2.00		
	Fourth floor	Nos	1					0.00		
	Head Room	Nos	1	1				1.00		
						Total Qty Work Done		45.00		
						Upto 125%		8.00	220	1760.00
						Above 125%		37.00	220	8140.00
120	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. - 10-12 Module ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No.3.5.5 P 9)									
	Ground floor									
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	2				2.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	First floor	Nos								
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	2				2.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Second floor	Nos								
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	2				2.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Third floor	Nos								
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	2				2.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		

Scanned with CamScanner

	Class room 5	Nos	1	2				2.00			
	Class room 6	Nos	1	2				2.00			
	Class room 7	Nos	1	2				2.00			
	Fourth floor	Nos									
	Head Room	Nos	1	2				2.00			
					Total Qty Work Done			104.00			
					Upto 125%			5.00	253	1265.00	
					Above 125%			99.00	253	25047.00	
121	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A - 6Amps one way ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of										
	Ground floor										
	Office 1 & 2	Nos	1	64				64.00			
	Toilet (class room)	Nos	1	13				13.00			
	Class room 1	Nos	1	15				15.00			
	Class room 2	Nos	1	15				15.00			
	Class room 3	Nos	1	15				15.00			
	Staircase	Nos	1	2				2.00			
	Class room 4	Nos	1	15				15.00			
	Class room 5	Nos	1	15				15.00			
	Class room 6	Nos	1	15				15.00			
	Class room 7	Nos	1	15				15.00			
	Corridor	Nos	1	12				12.00			
	First floor	Nos	1					0.00			
	Office 1 & 2	Nos	1	64				64.00			
	Toilet (class room)	Nos	1	13				13.00			
	Class room 1	Nos	1	15				15.00			
	Class room 2	Nos	1	15				15.00			
	Class room 3	Nos	1	15				15.00			
	Staircase	Nos	1	2				2.00			
	Class room 4	Nos	1	15				15.00			
	Class room 5	Nos	1	15				15.00			
	Class room 6	Nos	1	15				15.00			
	Class room 7	Nos	1	15				15.00			
	Corridor	Nos	1	12				12.00			
	Second floor	Nos	1					0.00			
	Office 1 & 2	Nos	1	64				64.00			
	Toilet (class room)	Nos	1	13				13.00			
	Class room 1	Nos	1	15				15.00			
	Class room 2	Nos	1	15				15.00			
	Class room 3	Nos	1	15				15.00			
	Staircase	Nos	1	2				2.00			
	Class room 4	Nos	1	15				15.00			
	Class room 5	Nos	1	15				15.00			
	Class room 6	Nos	1	15				15.00			
	Class room 7	Nos	1	15				15.00			
	Corridor	Nos	1	12				12.00			
	Third floor	Nos	1					0.00			
	Office 1 & 2	Nos	1	64				64.00			
	Toilet (class room)	Nos	1	13				13.00			
	Class room 1	Nos	1	15				15.00			
	Class room 2	Nos	1	15				15.00			
	Class room 3	Nos	1	15				15.00			
	Staircase	Nos	1	2				2.00			
	Class room 4	Nos	1	15				15.00			
	Class room 5	Nos	1	15				15.00			
	Class room 6	Nos	1	15				15.00			
	Class room 7	Nos	1	15				15.00			
	Corridor	Nos	1	12				12.00			

Scanned with CamScanner

	Fourth floor	Nos						0.00		
	Head Room	Nos	1	15				15.00		
					Total Qty Work Done			799.00		
					Upto 125%			50.00	77	3850.00
122	6Amps Two Way				Above 125%			749.00	77	57673.00
		Nos	1	1.00	30			30.00		
123	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A - 6Amps 3way socket. ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer									
	Ground floor									
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	3				3.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Staircase	Nos	1					0.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Corridor	Nos	1	2				2.00		
	First floor	Nos	1					0.00		
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	3				3.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Staircase	Nos	1					0.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Corridor	Nos	1	2				2.00		
	Second floor	Nos	1					0.00		
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	3				3.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Staircase	Nos	1					0.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Corridor	Nos	1	2				2.00		
	Third floor	Nos	1					0.00		
	Office 1 & 2	Nos	1	8				8.00		
	Toilet (class room)	Nos	1	3				3.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Staircase	Nos	1					0.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Corridor	Nos	1	2				2.00		
	Fourth floor	Nos						0.00		

Scanned with CamScanner

	Head Room	Nos	1	2				2.00		
					Total Qty Work Done			110.00		
					Upto 125%			13.00	115	1495.00
					Above 125%			97.00	115.40	11193.32
124	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A - Stepped Fan Regulator. ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No. 3.6.4 Page 10)									
	Ground floor									
	Office 1 & 2	Nos	1	4				4.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	First floor	Nos						0.00		
	Office 1 & 2	Nos	1	4				4.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Second floor	Nos						0.00		
	Office 1 & 2	Nos	1	4				4.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Third floor	Nos						0.00		
	Office 1 & 2	Nos	1	4				4.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
	Fourth floor	Nos						0.00		
	Head Room	Nos	1	2.00				2.00		
					Total Qty Work Done			82.00		
					Upto 125%			13.00	319.00	4147.00
					Above 125%			69.00	318.71	21990.99
125	16Amps one Way Switch									
		Nos	1	1	40			40		
126	6/16Amps Universal Socket									
		Nos	1	1	24			24		
127	Supplying 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire									

Scanned with CamScanner

		Nos	1	1	900			900			
128	Supplying and fixing one of 230 volts Ding dong bell and a flush type bell push with gang box fixed on										
		Nos	1	1	6			6			
129	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not										
		Nos	1	1	50			50			
130	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary										
		Nos	1	1	10			10			
131	Supplying of on load change over switches 4 poles, AC-23A Duty, 415V, 50Hz, AC Supply. With all										
		Nos	1	1	2			2			
132	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting Made out of 14 SWG MS enclosure.III - Double Door - 6Way TP &N ---- etc., complete with all lead & lift, as per specifications and as per directions of the										
	All the floors (5 x 2 Nos)	Nos	1	10.00				10.00			
					Total Qty Work Done			10.00			
					Upto 125%			3.00	7693		23079.00
					Above 125%			7.00	7693		53851.00
133	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. - 5-32Amps SP ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No.5.17.1 Page 27)										
	All the DBs (10 x 18 Nos)	Nos	1	180				180.00			
					Total Qty Work Done			180.00			
					Upto 125%			5.00	477		2385.00
					Above 125%			175.00	477		83475.00
134	5-32 Amps Dp. Group'A'										
		Nos	1	1	4			4			
135	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. - 40-63Amps TPN ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No.5.17.2 Page 27)										
		Nos	1	1	2			2			
136	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. - 40-63Amps TPN ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the										
	All the DBs (10 x 1 No) &	Nos	1	20				20.00			
					Total Qty Work Done			20.00			
					Upto 125%			3.00	2634		7902.00
					Above 125%			17.00	2634		44778.00
137	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door----										
		Nos	1	1	2			2			
138	4 way TPN										
		Nos	1	1	2			2			
139	6 Way TPN										
		Nos	1	1	2			2			
140	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. - 63Amps ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.5.5.2 Page 52)										
	BESCOM pole	Nos	1	3.00				3.00			
					Total Qty Work Done			3.00	4066		12198.00
141	32 Apms 4 pole										
		Nos	1	1	2			2			
142	Supplying, fixing and wiring earth leakage relay with core balanced current transformer suitable for										
		Nos	1	1	2			2			
143	Supplying, fixing and wiring 3 Phase Digital Ammeter /Voltmeter.										
		Nos	1	1	4			4			
144	Supplying of multi function digital meter with three line back light LCD type display for voltage, Current,										

Scanned with CamScanner

145	Supplying, fixing and wiring 50/5 to 400/5Amps 5VA burden Current Transformer. Class 0.5 accuracy	Nos	1	1	2			2		
		Nos	1	1	4			4		
146	Supplying, fixing and wiring electronic 5 to 32/63 Amps three phase 4 wire class-1 Accuracy Energy Meter. ---- etc , complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No 5 35 Page 29)									
	meter board	Nos	1	1.00				1.00		
					Total Qty Work Done			1.00	5215	5215.00
147	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C, 50 Hz 12/24v D.C.									
		Nos	1	1	6			6		
148	Supplying, fixing and wiring heavy duty low voltage capacitors conforming to IS 2834. 3 phase, 400/440 volts grade, for power factor improvement of rotating machineries like induction motor.									
		Nos	1	1	10			10		
149	Supplying ..... amps rated 3phase with neutral bus bar using required capacity electrolytic aluminum strips covered with heat shrinkable coloured PVC sleeve, mounted on phenolic/FRP/ DMC insulator which are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete.									
		Mtr	1	1	12			12		
150	Supplying and fixing angle iron frame work fabricated out of M.S. angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.-------									
		Mtr	1	1	12			12		
151	50X100X50X6mm C channel 50*6mm									
		Mtr	1	1	10			10		
152	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete. - 14SWG ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work. (Item No.5.42.1 Page 30)									
	Meter board	sq.cms	1	4		120.00	80.00	38400.00		
		sq.cms	1	8		120.00	40.00	38400.00		
		sq.cms	1	5		80.00	40.00	16000.00		
						Total		92800.00		
	add 15 % for bending							13920.00		
						Total Qty Work Done		106720.00		
						Upto 125%		100000	1	100000.00
						Above 125%		6720.00	0.44	2956.80
153	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.2 Page 40)									
	meter board	Nos	1	2.00				2.00		
						Total Qty Work Done		2.00	3297	6594.00
154	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm all-round with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts.									
		Nos	1	1	2			2		
155	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip									
		Mtr	1	1	8			8		
156	Cpopper Strip 25 X 3mm									
		Mtr	1	1	6			6		

Scanned with CamScanner

157	Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. GI Wire - 8 SWG ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.7.22.3 Page 70)									
	Earth pit to meter board	Mtr	1	2	25.00			50.00		
					Total Qty Work Done			50.00	64	3200.00
158	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A - 4 core 25 sqmm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.4.5 Page 40)									
	BESCOM pole ro meter	Mtr	1	2	70.00			140.00		
					Total Qty Work Done			140.00		
						Upto 125%		38	198	7524.00
						Above 125%		102.00	198	20196.00
159	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. - 25 sqmm to 95 sqmm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.5.2 Page 41)									
	BESCOM pole ro meter	Mtr	1	2	70.00			140.00		
					Total Qty Work Done			140.00		
						Upto 125%		25	17	425.00
						Above 125%		115.00	17	1955.00
160	On wall steucture.25 sqmm to 75 sqmm									
		Mtr	1	1.00	20			20.00		
161	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) - In soil (hard) ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.6.2 Page 41)									
	BESCOM pole ro meter	Mtr	1	2	60.00			120.00		
					Total Qty Work Done			120.00		
						Upto 125%		38	112	4256.00
						Above 125%		82.00	112	9184.00
162	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150mm all-round the cable.									
		Mtr	1	1.00	30			30.00		
163	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV. - 65mm ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.9.3 Page 42)									
	BESCOM pole to meter	Mtr	1	2	5.00			10.00		
					Total Qty Work Done			10.00	622	6220.00
164	Supplying and fixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) - 45mm dia ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.11.4 Page 42)									
	meter board	Nos	1	2.00				2.00		
					Total Qty Work Done			2.00	129	258.00
165	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes.------ ----2.5Sqmm									
		Nos	1	1	40			40		
166	4sqmm									
		Nos	1	1	30			30		
167	6sqmm									
		Nos	1	1	24			24		
168	10sqmm									
		Nos	1	1	24			24		
169	25sqmm Long Barrel									
		Nos	1	1	30			30		
170	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. 48" Sweep (1200mm) - Regular model ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.7.4.1 Page 46)									
	Ground floor									

Scanned with CamScanner

	Office 1 & 2	Nos	1	4				4.00		
	Class room 1	Nos	1	2				2.00		
	Class room 2	Nos	1	2				2.00		
	Class room 3	Nos	1	2				2.00		
	Class room 4	Nos	1	2				2.00		
	Class room 5	Nos	1	2				2.00		
	Class room 6	Nos	1	2				2.00		
	Class room 7	Nos	1	2				2.00		
					Total Qty Work Done			18.00		
					Upto 125%			18.00	3187	57366.00
171	Supplying & fixing retrofit type -PL- LED Lamp 8-9W LED linear source with CCT 6500 degree K, CRI> 70%, efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to beintegrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to275 volts. Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. 8-9 Watts									
		Nos	1	1.00	51			51.00		
172	Supplying of .....feet - PVC Batten with integrated LED tube.....W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition.LED light fighting 1 x4'- 20/22 w									
		Nos	1	1.00	28			28.00		
173	LED light fighting 2X4' - 20/22 W									
		Nos	1	1.00	10			10.00		
174	Fixing all types and all capacities of fluorescent /False ceiling/spot light /CFL/LED fittings indoor on the wall/ ceiling/rafters/girders using 23/0.0076' twin twisted PVC insulated wires, required Nos of round blocks and clamps. (114/17.7)c) Using 1 Mtr long 19mm 18 SWG enameled brazed conduit of two nos rod pendent with ball socket with check nuts all nickel plated ---- Including cost of all materials, with all lead, lift and labour charges etc., complete as directed by the Engineer-in-charge of the work.(Item No.14.7.1 Page 79)									
	Ground floor									
	Office 1 & 2	No	1	12		12.00		12.00		
	Toilet (class room)	No	1	3		3.00		3.00		
	Class room 1	No	1	6		6.00		6.00		
	Class room 2	No	1	6		6.00		6.00		
	Class room 3	No	1	6		6.00		6.00		
	Staircase	No	1	2		2.00		2.00		
	Class room 4	No	1	6		6.00		6.00		
	Class room 5	No	1	6		6.00		6.00		
	Class room 6	No	1	6		6.00		6.00		
	Class room 7	No	1	6		6.00		6.00		
	Corridor	No	1	11		11.00		11.00		
					Total Qty Work Done			70.00		
					Upto 125%			38.00	130	4940.00
					Above 125%			32.00	120.89	3868.48
175	KSRB 13-11 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM and testing complete as per specifications. (For 1000 litre capacity) Specification No.KBS 13.22									
		Nos	1	3				3		
		Nos	1	3				3		
					Total Qty Work Done			6		
					Upto 125%			3	8104.00	24312.00
					Above 125%			3	8104.00	24312.00

Scanned with CamScanner

176	Supplying 50 litres capacity vertical/horizontal type wall mounting Electrical water heater with 22 SWG copper/SS sheet metal inner Container tinned inside and anticorrosive paint outside and 20 SWG M.S. sheet metal outer cover filled with glass wool between inner and outer container for thermal insulation complete. The inlet and outlet pipes so arranged that water flow inside results in water to flow out from the inner container without turbulence. The Inner container shall have direct immersion type copper tube nickel plate ,2KW capacity element with a neon indicator fitted with 20A capacity 25 to 85 degree Centigrade range thermostat. The water heater shall completely be wired with 40/0.0076 inch 3 core copper flexible wire of 1.5 meters length and the outer container provided with heavy gauge brackets for									
		Nos	1	1	10			10		
EIRL 1	KSRB 6.32 : Providing and constructing non load bearing Wall with Light Weight Concrete (Autoclaved aerated concrete) Blocks Confirming to IS:2185 (part) 1984 and IS 6441-1972 of compressive Strength of 3.0N/sq mm with a thin layer of polymer based jiontig solvent for super structure with neccesary including cost of materials, labour charges, scaffolding, curing complete as per specifications. Item No. 6.32.2)									
	Second Floor & Third Floor									
	Room 2	Sqm	1	1	6.75		3.40	22.95		
	Office Room	Sqm	2	1	7.65		3.40	52.02		
	Deduct Beam	Sqm	3	1	0.20		0.45	-0.27		
	Head Room									
	Long Wall	Sqm	2	1	6.55		3.30	43.23		
	Short Wall	Sqm	2	1	5.75		3.30	37.95		
	Deduct Door	Sqm	1	1	1.20		2.40	-2.88		
	Deduct Window	Sqm	1	2	1.50		1.50	-4.50		
					Total Qty Work Done			153.00	1856.34	284020.46
EIRL 2	KSRB 5-14 : Providing and constructing percast concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, jamb closer blocks) with solid concrete blocks of size 40x10x20cms conforming to I.S : 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (Issue rate as on date 21-10-19, Item									
	Ground Floor	Sqm	2	1	6.75		2.40	32.40		
		Sqm	2	4	1.45		2.40	27.84		
	Deduct Door	Sqm	2	5	0.90		2.10	-18.90		
	Deduct Lintel	Sqm	2	1	6.75		0.10	-1.35		
		Sqm	2	4	1.45		0.10	-1.16		
	First Floor	Sqm	2	1	6.75		2.40	32.40		
		Sqm	2	4	1.45		2.40	27.84		
	Deduct Door	Sqm	2	5	0.90		2.10	-18.90		
	Deduct Lintel	Sqm	2	1	6.75		0.10	-1.35		
		Sqm	2	4	1.45		0.10	-1.16		
	Second Floor	Sqm	2	1	6.75		2.40	32.40		
		Sqm	2	4	1.45		2.40	27.84		
	Deduct Door	Sqm	2	5	0.90		2.10	-18.90		
	Deduct Lintel	Sqm	2	1	6.75		0.10	-1.35		
		Sqm	2	4	1.45		0.10	-1.16		
	Third Floor	Sqm	2	1	6.75		2.40	32.40		
		Sqm	2	4	1.45		2.40	27.84		
	Deduct Door	Sqm	2	5	0.90		2.10	-18.90		
	Deduct Lintel	Sqm	2	1	6.75		0.10	-1.35		
		Sqm	2	4	1.45		0.10	-1.16		
	StairCase Pin Box	Sqm	2	2	14.27		0.15	8.56		
			2	2	1.75		0.15	1.05		
					Total Qty Work Done			164.93	1033.81	170507.91

Scanned with CamScanner

EIRL 3	KSRB15-3.11 : Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications										
	Terrace	Sqm	1	1	43.60	16.92		737.71			
	Head Rooms	Sqm	2	1	3.60	4.16		29.95			
		Sqm	1	1	6.95	6.57		45.66			
	Deduct Head Rooms	Sqm	2	1	3.60	4.16		-29.95			
		Sqm	1	1	6.95	6.57		-45.66			
					Total Qty Work Done			737.71	343.02	253049.85	
EIRL 4	KSRB15-4.5 Extra for providing and mixing waterproofing compound in cement plaster for stone masonry work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:4, 20mm thick cost of materials complete as per specifications.										
	Terrace	Sqm	1	1	43.60	16.92		737.71			
	Head Rooms	Sqm	2	1	3.60	4.16		29.95			
		Sqm	1	1	6.95	6.57		45.66			
	Deduct Head Rooms	Sqm	2	1	3.60	4.16		-29.95			
		Sqm	1	1	6.95	6.57		-45.66			
					Total Qty Work Done			737.71	24.93	18387.71	
EIRL 5	KSRB15-6 : Providing floating coat of cement to plastering and finishing smooth, including cost of materials, labour, curing complete as per specifications.										
	Terrace	Sqm	1	1	43.60	16.92		737.71			
	Head Rooms	Sqm	2	1	3.60	4.16		29.95			
		Sqm	1	1	6.95	6.57		45.66			
	Deduct Head Rooms	Sqm	2	1	3.60	4.16		-29.95			
		Sqm	1	1	6.95	6.57		-45.66			
					Total Qty Work Done			737.71	36.79	27143.76	
EIRL 6	KSRB 15.9 Providing and fixing Corner beads 45x45mm size manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls,columns,lintels including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment) ---- The work shall be carried out as per standard technical detailed specifications and as directed by the Engineer in charge of the work										
	Second Floor Inside										
	Room 5 &8	RMt	2	5			2.95	10.00			
		RMt	2	1	5.40			10.80			
		RMt	2	1	3.20			6.40			
		RMt	2	1	4.17			8.34			
	Room 6&7	RMt	2	5			2.95	29.50			
		RMt	2	1	6.85			13.70			
		RMt	2	1	1.30			2.60			
		RMt	2	1	3.65			7.30			
	Room 1,4	RMt									
		RMt	2	10			2.95	59.00			
		RMt	2	1	6.20			12.40			
		RMt	2	4	5.40			43.20			
	Room 2,3	RMt	1	12			2.95	12.00			
		RMt	1	4	5.40			21.60			
		RMt	1	2	4.10			8.20			
	Third Floor Inside	RMt									
	Room 4 &7	RMt	2	5			2.95	10.00			
		RMt	2	1	5.40			10.80			
		RMt	2	1	3.20			6.40			
		RMt	2	1	4.17			8.34			
	Room 5&6	RMt	2	5			2.95	29.50			

Scanned with CamScanner

		RMt	2	1	6.85			13.70		
		RMt	2	1	1.30			2.60		
		RMt	2	1	3.65			7.30		
	Room 1,3	RMt								
		RMt	2	10			2.95	59.00		
		RMt	2	1	6.20			12.40		
		RMt	2	4	5.40			43.20		
	Room 2	RMt	1	12			2.95	12.00		
		RMt	1	4	5.40			21.60		
		RMt	1	2	4.10			8.20		
						Total Qty Work Done		490.08	47.48	23267.43
EIRL 7	KSRB 15.8.2 Providing and fixing plaster mesh 150mm wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications,The work shall be carried out as per standard technical detailed specifications and as directed by the Engineer in charge of the work									
	Second Floor Inside									
	Passage									
		RMt	2	1	2.15			4.30		
		RMt	2	6	5.40			64.80		
		RMt	1	16			3.40	54.40		
		RMt	2	10			3.40	68.00		
		RMt	2	1	6.17			12.34		
		RMt	1	1	6.55			6.55		
		RMt	2	1	4.10			8.20		
		RMt	2	1	6.85			13.70		
		RMt	2	1	1.30			2.60		
	Room 2 &3	RMt	2	1	6.20			12.40		
	Room 5 &8	RMt	2	2			2.95	4.00		
		RMt	2	1	3.20			6.40		
		RMt	2	1	4.17			8.34		
	Room 6&7	RMt	2	2			2.95	11.80		
		RMt	2	1	6.17			12.34		
		RMt	2	1	3.20			6.40		
	Third Floor Inside	RMt								
	Passage									
		RMt	2	1	2.15			4.30		
		RMt	2	6	5.40			64.80		
		RMt	1	16			3.40	54.40		
		RMt	2	10			3.40	68.00		
		RMt	2	1	6.17			12.34		
		RMt	1	1	6.55			6.55		
		RMt	2	1	4.10			8.20		
		RMt	2	1	6.85			13.70		
		RMt	2	1	1.30			2.60		
	Room 2	RMt	1	2	6.20			12.40		
	Room 4 & 5	RMt	2	2			2.95	4.00		
		RMt	2	1	3.20			6.40		
		RMt	2	1	4.17			8.34		
	Room 3 & 6	RMt	2	2			2.95	11.80		
		RMt	2	1	6.17			12.34		
		RMt	2	1	3.20			6.40		
						Total Qty Work Done		593.14	51.04	30272.42
EIRL 8	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - 40mm thick both side commercial ---- including cost and conveyance of all materials, all labour, all lead and lifts, loading & unloading chares, hire charges of all machinery and equipments and all other incidental charges. The work shall be carried out as per standard technical detailed specifications and as directed by the Engineer in charge of the									
	Ground Floor	Sqm	1	11	1.04		2	22.88		

Scanned with CamScanner

	First Floor	Sqm	1	1	1.04		2	2.08		
	Ground Floor Toilet Room	Sqm	2	1	1.04		2	4.16		
	First Floor Toilet Room	Sqm	2	1	1.04		2	4.16		
	Second Floor Toilet Room	Sqm	2	1	1.04		2	4.16		
	Third Floor Toilet Room	Sqm	2	1	1.04		2	4.16		
	Head Room	Sqm	1	1	1.04		2	2.08		
					Total Qty Work Done			43.68	3315.07	144802.16
EIRL 9	uPvC Windows and Doors - Providing & fixing of glazed 2 Track-2 Panel Sliding Windows made out of multi Chamered uPVC sections with TPV gaskets having Isolated drainage and reinforced witgh Galvanized iron profiles through out the window. The outer frame having a overall size of 60x45 mm with reinforcement of 1 mm thickness and sash with overall size of 39x58 mm with reinforcement of 1.5mm thickness. Glazing bead for fixing ofglass shall be of size 20x18mm and coextruded with gasket. Windows shall be provided with 5mm plain float glass, standard hardware & single point locking system of flush lock, Wall thickness of frame & sash shall be 2-2.2 mm. ---- including cost and conveyance of all materials, all labour, all lead and lifts, loading & unloading chares, hire charges of all machinery and equipments and all other incidental charges. The work shall be carried out as per standard technical									
	Ground Floor									
	Room 1,2,3,4,5,6	Sqm	6	2	1.50		1.50	27.00		
	Landscape	Sqm	1	2	1.20		1.50	3.60		
	Office 1&2	Sqm	2	4	1.80		1.50	21.60		
	Room 7,8	Sqm	2	2	1.20		1.50	7.20		
	StairCase	Sqm	2	1	1.20		1.50	3.60		
	First Floor									
	StairCase	Sqm	2	1	1.20		1.50	3.60		
		Sqm	1	1	1.20		1.50	1.80		
					Total Qty Work Done			68.40	3591.62	245666.80
EIRL 10	uPvC Windows and Doors - Providing & of Fixed Louvered Ventilator made out of multi chambered uPVC sections with TPv gaskets having isolated drainage and reinforced with Galvanized Iron profiles through out the windown. The outer frame having a overall size of 60x55mm with reinforcement of 1 mm thickness and Mullion with overall size of 74x60mm with reinforcement of 1 mm thickness. Ventilator shall be provided with 4.5 mm Pin Head glass, standard hardware, Wall thickness of frame Mullion shall be 2-2.2 mm. ---- including cost and conveyance of all materials, all labour, all lead and lifts, loading & unloading chares, hire charges of all machinery and equipments and all other incidental charges. The work shall be carried out as per standard technical detailed specifications and as directed by the									
	Ground Floor									
	Ventilator	Sqm	6	1	1.2		0.4	1.44		
	Toilet G.floor	Sqm	2	1	2.75		0.60	3.30		
		Sqm	2	1	6.15		0.60	7.38		
	Toilet F.floor	Sqm	2	1	2.75		0.60	3.30		
		Sqm	2	1	6.15		0.60	7.38		
	Toilet S.floor	Sqm	2	1	2.75		0.60	3.30		
		Sqm	2	1	6.15		0.60	7.38		
	Toilet T.floor	Sqm	2	1	2.75		0.60	3.30		
		Sqm	2	1	6.15		0.60	7.38		
					Total Qty Work Done			44.16	4310.89	190369.05
EIRL 11	Supplying of 1440rpm heavy duty exhaust fan with bracket blades suitable to operate on 230V 50Hz, AC Supply complete.(7.2.1/46)									
	Ground floor									
	Toilet (class room)	No	1	4				4.00		
	First floor									
	Toilet (class room)	No	1	4				4.00		
	Second floor									
	Toilet (class room)	No	1	4				4.00		
	Third floor									
	Toilet (class room)	No	1	4				4.00		
					Total Qty Work Done			16.00	2492.53	39880.51
EIRL 12	Fixing one exhaust fan after making a suitable nitch in the wall and finishing with cement mortar and colouring to match the existing wall or brackets with bolts and nuts and a 5 amps, ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire of approved make with wire mesh and									
	Ground floor									
	Toilet (class room)	No	1	4				4.00		
	First floor	No								

Scanned with CamScanner

	Toilet (class room)	No	1	4				4.00		
	Second floor	No								
	Toilet (class room)	No	1	4				4.00		
	Third floor	No								
	Toilet (class room)	No	1	4				4.00		
						Total Qty Work Done		16.00	771.50	12343.97
EIRL 13	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc. - 50Sqmm -- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.6.10.5 Page 42)									
	BESCOM pole	Nos	1	2.00				2.00		
						Total Qty Work Done		2.00	213.65	427.29
EIRL 14	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker [ELMCB] 240/450V up to 300mA sensitivity on existing wood/panel board. - 32-40 Amps 4 pole ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.5.20.3 Page									
	Meter board	Nos	1	1.00				1.00		
						Total Qty Work Done		1.00	3323.38	3323.38
EIRL 15	Supplying, fixing and wiring Residual current Circuit Breaker [RCCB] 240/450V up to 300mA sensitivity on existing wood/panel board.63A 4 pole (5.19.10)									
	All the DBs (10 x 1 No)	Nos	1	10.00				10.00		
						Total Qty Work Done		10.00	5697.22	56972.16
EIRL 16	Supplying box type suitable for 28W T5 single / twin Lamp & suspension mounted luminaire & optical reflector. Prewired with HF electronic Ballast, push fit type lamp holders & main connectors. Channel cover shall be made of CRCA MS Sheet and finishing is done with stove enameled white with end caps made of engineering plastic. - 1x4'-28 Watts ---- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work.(Item No.12.3.2 Page 64)									
	Ground floor									
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	3				3.00		
	Class room 1	No	1	6				6.00		
	Class room 2	No	1	6				6.00		
	Class room 3	No	1	6				6.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	6				6.00		
	Class room 5	No	1	6				6.00		
	Class room 6	No	1	6				6.00		
	Class room 7	No	1	6				6.00		
	Corridor	No	1	11				11.00		
	First floor							0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	3				3.00		
	Class room 1	No	1	6				6.00		
	Class room 2	No	1	6				6.00		
	Class room 3	No	1	6				6.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	6				6.00		
	Class room 5	No	1	6				6.00		
	Class room 6	No	1	6				6.00		
	Class room 7	No	1	6				6.00		
	Corridor	No	1	11				11.00		
	Second floor							0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	3				3.00		
	Class room 1	No	1	6				6.00		
	Class room 2	No	1	6				6.00		
	Class room 3	No	1	6				6.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	6				6.00		
	Class room 5	No	1	6				6.00		

Scanned with CamScanner

	Class room 6	No	1	6				6.00		
	Class room 7	No	1	6				6.00		
	Corridor	No	1	11				11.00		
	Third floor							0.00		
	Office 1 & 2	No	1	12				12.00		
	Toilet (class room)	No	1	3				3.00		
	Class room 1	No	1	6				6.00		
	Class room 2	No	1	6				6.00		
	Class room 3	No	1	6				6.00		
	Staircase	No	1	2				2.00		
	Class room 4	No	1	6				6.00		
	Class room 5	No	1	6				6.00		
	Class room 6	No	1	6				6.00		
	Class room 7	No	1	6				6.00		
	Corridor	No	1	11				11.00		
	Fourth floor							0.00		
	Head Room	No	1	6				6.00		
							Total Qty Work Done	286.00	445.10	127297.17
EIRL 17	Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps. --- etc., complete with all lead & lift, as per specifications and as per directions of the Engineer in charge of the work (Item No.4.2.1 Page 20)									
	Ground floor									
	Office 1 & 2	No	1	16				16.00		
	Toilet (class room)	No	1	4				4.00		
	Class room 1	No	1	2				2.00		
	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Staircase	No	1					0.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Corridor	No	1	10				10.00		
	First floor	No	1					0.00		
	Office 1 & 2	No	1	16				16.00		
	Toilet (class room)	No	1	4				4.00		
	Class room 1	No	1	2				2.00		
	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Staircase	No	1					0.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Corridor	No	1	10				10.00		
	Second floor	No	1					0.00		
	Office 1 & 2	No	1	16				16.00		
	Toilet (class room)	No	1	4				4.00		
	Class room 1	No	1	2				2.00		
	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Staircase	No	1					0.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Corridor	No	1	10				10.00		
	Third floor	No	1					0.00		
	Office 1 & 2	No	1	16				16.00		

Scanned with CamScanner

	Toilet (class room)	No	1	4				4.00		
	Class room 1	No	1	2				2.00		
	Class room 2	No	1	2				2.00		
	Class room 3	No	1	2				2.00		
	Staircase	No	1					0.00		
	Class room 4	No	1	2				2.00		
	Class room 5	No	1	2				2.00		
	Class room 6	No	1	2				2.00		
	Class room 7	No	1	2				2.00		
	Corridor	No	1	10				10.00		
	Fourth floor	No	1					0.00		
	Class room 3	No	1	2				2.00		
						Total Qty Work Done		178.00	100.89	17958.10
EIRL 18	Providing textured paint of approved quality, colour and shade to wall surface after cleaning and rubbing the wall surface with wire brush of medium size emery stone to remove all the loosely adhering particles, the surface is then cleaned with water and ensured that it is in line and level. The textured material is then mixed with 40-50% of clean water until a homogeneous thick slurry is formed, the slurry is left for 5-10 min, to react completely with ingredients. The textured finish prepared as above is then applied to the wall surface with suitable roller/spray gun/putty/ blade/ trowel to get the desired finish. The finished surface shall be applied with two coats of exterior paint of approved shade. The rate includes providing and removing scaffolding, all lead and lift and all other incidental charges etc., complete as per directions of the Engineer-in-charge o f the work . (PWD -SZB-SR 2018-19, P-128, I-									
	Front View									
	A'2 to A2,N2 to N'2	Sqm	2	1	2.60		3.55	18.46		
	A2 to C2 & L2 to N2	Sqm	2	1	4.40		3.55	31.24		
		Sqm	2	1	4.40		3.55	31.24		
	Pin Wall	Sqm	2	1	1.40		3.55	9.94		
	Chajja	Sqm	2	1	3.80		1.30	9.88		
	Deduct Windows	Sqm	4	1/2	1.80		1.50	-5.40		
	Deduct Chajja	Sqm	2	1	0.15		0.60	-0.09		
	C2 to D2 & K2 to L2	Sqm	2	1	3.30		3.55	23.43		
		Sqm	2	1	2.30		3.55	16.33		
		Sqm	2	1	2.50		3.55	17.75		
	Deduct Windows	Sqm	2	1/2	1.40		1.20	-1.68		
	D2 to F2 & I2 to K2	Sqm	2	1	3.75		3.55	26.63		
		Sqm	2	1	3.75		3.55	26.63		
	Pin Wall	Sqm	2	1	1.40		3.55	9.94		
	Chajja	Sqm	2	1	2.60		1.30	6.76		
	Deduct Windows	Sqm	2	1/2	1.20		1.50	-1.80		
	Deduct Beam	Sqm	2	1	0.20		0.60	-0.24		
	Portico Beam F1 to F2	Sqm	2	1	5.35		0.60	6.42		
	Chajja	Sqm	2	1	5.35		0.70	7.49		
	Beam F1 to I1	Sqm	1	1	6.95		0.60	4.17		
	Chajja	Sqm	1	1	8.05		0.70	5.64		
	A'2 to A'7 & N'2 to N'7	Sqm	2	1	2.45		3.55	17.40		
		Sqm	2	1	16.00		3.55	113.60		
	Chajja	Sqm	2	1	4.10		0.70	5.74		
	Deduct Windows	Sqm	4	1/2	1.80		1.50	-5.40		
	Deduct Windows	Sqm	2	1/2	1.50		1.50	-2.25		
	B8 to M8	Sqm	6	1	5.40		3.55	115.02		

Scanned with CamScanner

		Sqm	1	1	4.10		3.55	14.56		
		Sqm	2	1	2.75		3.55	19.53		
	Column A'8,B8,C8,E8,G8,h8,J8,L8, M8,N'8	Sqm	11	1	1.34		3.55	52.33		
	Chajja	Sqm	6	2	1.80		1.40	30.24		
		Sqm	6	4	0.60		0.10	1.44		
	Deduct Windows	Sqm	12	1/2	1.50		1.50	-13.50		
	Deduct Windows	Sqm	1	1/2	1.20		1.50	-0.90		
	Deduct Door	Sqm	1	1/2	1.20		2.40	-1.44		
					Total Qty Work Done			589.08	213.65	125853.71
						Present Amount				28253001.92

28253025.00

CERTIFICATE

1) Certified that the Estimate prepared with necessary provisions as Per site conditions.

2) Certified that the estimate is prepared on the basis of PW,P & IWTD Bangalore Circle, for the year 2018-19 and Data Approved Rate

3) Certified that the above area comes under BBMP limits

Assitant Engineer
Ward No-16,
BBMP

Asst. Executive Engineer
Yeshwanthpura Sub-Division
BBMP

Executive Engineer
Rajarajeshwari Nagara Division
BBMP

Bruhat Bangalore Mahanagara Palike

Modified.

TECHNICAL SANCTION

Rs: 28 25 3025/- (Rupees Two crore Eight two lakhs fifty three thousand twenty five only) is accorded under the head: P- 3853

By CE(R.R.N.), P.N.-20-21

Registered as CE (R.R.N No. 63/1/22-23 subject to conditions contained in enclosed memo No: 63/1/22-23 Dated: 08/7/22

TA,

CE (R.R.N.)

Scanned with CamScanner